

CODE NO	PAY ITEM	UNIT	TOTAL
			QUANTITY ROADWAY (000)
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	293
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	293
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	439
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	22
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	22
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	22
25200110	SODDING, SALT TOLERANT	SQ YD	439
35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	11
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	215
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	121
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2881
40600300	AGGREGATE (PRIME COAT)	TON	58
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	7
X4040821	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	807
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	113
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	221
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	24
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1210
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	58
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1740
42400800	DETECTABLE WARNINGS	SQ FT	144
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	14290
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	271
44000600	SIDEWALK REMOVAL	SQ FT	1969
Z0008021	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1279
44002210	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/2"	SQ YD	1432
44200978	CLASS B PATCHES, TYPE I, 11 INCH	SQ YD	39
44200982	CLASS B PATCHES, TYPE II, 11 INCH	SQ YD	39
44200986	CLASS B PATCHES, TYPE III, 11 INCH	SQ YD	39
44200988	CLASS B PATCHES, TYPE IV, 11 INCH	SQ YD	39
44201737	CLASS D PATCHES, TYPE I, 8 INCH	SQ YD	358
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	358
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	358
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	358
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	8
67100100	MOBILIZATION	L SUM	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1

* = SPECIALTY ITEM

CODE NO	PAY ITEM	UNIT	TOTAL
			QUANTITY ROADWAY (000)
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1117
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	152
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4469
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4047
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	350
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	180
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3440
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	152
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4469
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4047
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	350
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	180
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	21
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1909
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	74
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	138
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	45
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	120
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51
Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	4



DESIGNED BY KB
DRAWN BY IS
CHECKED BY DL
DATE 6/17/10

REVISIONS
REVISIONS
REVISIONS
REVISIONS

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. 3 OF SHEETS STA. TO STA.

F.A.U. SECTION COUNTY TOTAL SHEET NO.
RTE. 1574 10-00175-00-RS COOK 20 3
CONTRACT NO. 63497
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT