SUMMARY OF QUANTITIES

	CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
					ROADWAY I000-2A	TRAFFIC SIGNALS Y031-1F
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	95	95	-
	20101100	TREE TRUNK PROTECTION	EACH	4	4	-
*	20101200	TREE ROOT PRUNING	EACH	4	4	-
*	20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	4	4	-
*	20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	4	4	-
	20200100	EARTH EXCAVATION	CU YD	1,446	1,446	-
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	387	387	-
	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	171	171	-
	20800150	TRENCH BACKFILL	CU YD	3,005	3,005	-
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	469	469	-
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2,958	2,958	-
*	25000110	SEEDING, CLASS 1A	ACRE	0.15	0.15	-
*	25000210	SEEDING, CLASS 2A	ACRE	0.49	0.49	-
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	60	60	-
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	60	60	-
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	60	60	-
*	25100630	EROSION CONTROL BLANKET	SQ YD	2,958	2,958	-
*	25200200	SUPPLEMENTAL WATERING	UNIT	38	38	-
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100	-
	28000400	PERIMETER EROSION BARRIER	FOOT	3,233	3,233	-
	28000510	INLET FILTERS	EACH	31	31	-
	28000700	MULCH, METHOD 1	ACRE	1.00	1.00	-
	31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	2,392	2,392	-
	31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	98	98	-
	35100040	STOCKPILING SALVAGED AGGREGATE	CU YD	843	843	-
	35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	109	109	-
	35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	198	198	-
	35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	10	10	-
	35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	40	40	-
	35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	2,020	2,020	-

* INDICATES SPECIALTY ITEM

COPYRIGHT © 2009, BY BAXTER & WOODMAN, INC.
STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
LICENSE NO. 184-001272 EXPIRES 4/30/2011
LAST REVISED 6/17/2010 4:24:44 PM
...\plotdriver\PDF22X34.pltcfg
...\pwworking\09\d0972432\sheet1.dgn
h:\Projects\1-Ldg\DRAWING\090772-Atkinson Ph1\CADD-SURVEY\DRAWINGS\DGNS\sheets\phase 2\090772-SMY-QTY-1.dgn

BAXTER & WOODMAN Consulting Engineers

DESIGNED - DJS	REVISED - 6-8-10 IDOT REVIEW	
DRAWN - UKB	REVISED -	
CHECKED - RWL	REVISED -	
DATE - 4-27-10	FILE - 090772-SMY-QTY-1.dgn	

VILLAGE OF GRAYSLAKE, ILLINOIS
ATKINSON ROAD RESURFACING
AND RECONSTRUCTION IMPROVEMENTS

SUMMARY OF QUANTITIES

SCALE: STA. TO STA.

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0198	09-00058-00-RS	LAKE	46	4

CONTRACT NO. 63498

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT: M-9003 (485)