SUMMARY OF QUANTITIES

	CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE ROADWAY I000-2A	CONSTRUCTION TYPE CODE TRAFFIC SIGNALS Y031-1F
*	88000490	SIGNAL HEAD, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1	-	1
*	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4	-	4
*	88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	6	-	6
*	88500100	INDUCTIVE LOOP DETECTOR	EACH	5	-	5
*	88600100	DETECTOR LOOP, TYPE I	FOOT	304	-	304
*	88700200	LIGHT DETECTOR	EACH	2	-	2
*	88700300	LIGHT DETECTOR AMPLIFIER	EACH	1	-	1
*	88800100	PEDESTRIAN PUSH-BUTTON	EACH	4	-	4
*	A2004816	TREE, GLEDITSIA TRIACANTHOS INERMIS SKYLINE (SKYLINE THORNLESS COMMON HONEYLOCUST), 2" CALIPER, BALLED AND BURLAPPED	EACH	2	2	-
*	A2006516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	4	4	-
*	B2005416	TREE, PRUNUS VIRGINIANA SCHUBERT (SCHUBERT CHOKEBERRY), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	2	2	-
*	B2006116	TREE, SYRINGA PEKINENSIS MORTON (CHINA SNOW PEKING LILAC), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	3	3	-
△	Z0076600	TRAINEES	HOUR	500	500	-
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	-
	X0326861	PULVERIZATION	SQ YD	2,020	2,020	-
	X0320139	TEMPORARY CONSTRUCTION FENCE	FOOT	1,380	1,380	-
	X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	146	146	-
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	390	390	-
	X0325279	CLASS SI CONCRETE (MISCELLANEOUS)	CU YD	9	9	-
	X0325608	GEOSYNTHETIC REINFORCEMENT	SQ YD	2,471	2,471	-
	X0325391	EXPANDED POLYSTYRENE FILL	CU YD	1,712	1,712	-
	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	1	1	-
*	X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1	-	1
*	X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	1	-	1
*	X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	998	-	998
*	X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	232	-	232

* INDICATES SPECIALTY ITEM

△ Y080

COPYRIGHT © 2005 BY BAXTER & WOODMAN, INC.
STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
LICENSE NO. 184-001107 EXPIRES 4/30/2011
Wednesday, 04/28/2010 4:52:42 PM
...\pbrdriver\PDF22X34.pltl
...\Phase1\090772-SMY-QTY-5.dgn
...\Project\DGN\GRAYL\090772-Atkinson Ph1\CADD-SURVEY\DRAWINGS\DGNS\sheets\phase 2\090772-SMY-QTY-5.dgn

BAXTER & WOODMAN Consulting Engineers

DESIGNED - DJS	REVISED - 6-8-10 IDOT REVIEW	VILLAGE OF GRAYSLAKE, ILLINOIS ATKINSON ROAD RESURFACING AND RECONSTRUCTION IMPROVEMENTS	SUMMARY OF QUANTITIES
DRAWN - UKB	REVISED -		
CHECKED - RWL	REVISED -		
DATE - 4-27-10	FILE - 090772-SMY-QTY-5.dgn		SCALE: STA. TO STA.

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0198	09-00058-00-RS	LAKE	46	8
		CONTRACT NO. 63498		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT: M-9003 (485)		