

EARTHWORK

LOCATION STA TO STA	1 UNDERCUT AND PGE REPLACEMENT (CY)	2 UNSUITABLE EXCAVATION (TOPSOIL) (CY)	3 REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL (CY)	4 EARTH EXCAVATION (CY)	5 UTILITY EXCAVATION (CY)	6 EXCESS STRUCTURE EXCAVATION (CY)	7 TOTAL SUITABLE EXCAVATION (CY)	8 EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) (CY)	9 EMBANKMENT (CY)	10 EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CY)
ATKINSON ROAD	161	181	342	1416	2975	0	4391	3733	652	3081
BRAE LOCH ROAD	10	35	45	30	5	0	35	30	5	25
TOTALS	171	216	387	1446	2980	0	4426	3763	657	3106

HOT-MIX ASPHALT SURFACE REMOVAL – BUTT JOINT

LOCATION	SQ YD
ATKINSON ROAD (47+70)	23
BRAE LOCH ROAD (50+98, 89' RT)	17
FREDERICK ROAD (56+17, 50' LT)	15
BLACKBURN DRIVE (56+17, 47' RT)	15
SHAKESPEARE DRIVE (59+66, 53' LT)	20
SHAKESPEARE DRIVE (71+19, 53' LT)	14
CAMBRIDGE DRIVE (74+62, 53' RT)	14
CHERRY CREEK DRIVE (77+67, 65' LT)	19
ATKINSON ROAD (82+10)	22
TOTAL	159

COPYRIGHT © 2009 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. - 34-0027206
 2600 S. M.
 10101 Driver VPRF2334.dwg
 10906
 090772-HK0000
 PH:\CAD\1-SURVEY\DRAWINGS\WORKSHEETS\Schedule_2\090772-SCHEDULE-01.dgn



DESIGNED -	DJS	REVISED -	
DRAWN -	UKB	REVISED -	
CHECKED -	RWL	REVISED -	
DATE -	4-27-10	FILE -	090772-SCHEDULE-QTY.dgn

**VILLAGE OF GRAYSLAKE, ILLINOIS
ATKINSON ROAD RESURFACING
AND RECONSTRUCTION IMPROVEMENTS**

SCHEDULE OF MATERIALS

SCALE: _____ STA. _____ TO STA. _____

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0198	09-00058-00-RS	LAKE	46	11
CONTRACT NO. 63498				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT: M-9003 (485)				