

**SUMMARY OF QUANTITIES**

F.A.U. RITE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3898	10-00024-00-RS	KANE	13	3
CONTRACT NO. 63499				

			CONST. CODE 1000
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,323
40600300	AGGREGATE (PRIME COAT)	TON	28
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	743
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	553
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,112
44201725	CLASS D PATCHES, TYPE I, 7 INCH	SQ YD	4
44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	14
44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQ YD	23
44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SQ YD	454
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	495
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,500
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	500
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	19,250
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	14
Δ * XX008398	ASPHALT REJUVENATING AGENT	GALLON	1,325
Δ * Z0010619	HOT IN-PLACE RECYCLING	SQ YD	13,226

Δ SEE SPECIAL PROVISIONS  
\* SPECIALTY ITEMS

COPYRIGHT © 2010 ENGINEERING ENTERPRISES, INC.

Plotted: June 8, 2010 @ 4:23 PM By: Larry Nolan - Tab: 03 Quantities - 22x34

**Engineering Enterprises, Inc.**  
CONSULTING ENGINEERS  
52 Wheeler Road  
Sugar Grove, Illinois 60554  
630.466.6700 / www.eeiweb.com

**VILLAGE OF SUGAR GROVE**  
KANE COUNTY, ILLINOIS

NO.	DATE	REVISIONS

**GRANART ROAD**  
**LAPP IMPROVEMENTS**

**SUMMARY OF QUANTITIES**

DATE:	JUNE 2010
PROJECT NO:	SG1012
FILE:	SG1012-CVR
SHEET	<b>3</b> OF <b>13</b>

Path: H:\S05\PROJ\SG0307\DWG\SG1012\DWG\_FINAL\_ENG\_SG1012-CVR