

PLAN SURVEYED BY DATE  
 NOTE BOOK NO. RT. OF WAY CHECKED  
 CADD FILE NAME

PROFILE SURVEYED BY DATE  
 GRADES CHECKED  
 STRUCTURE NOTATIONS CHECKED

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	SFTY - 1B	SFTY - 2A	NON-PARTICIPATING
				ROADWAY	BRIDGE	ROADWAY
20101200	TREE ROOT PRUNING	EACH	10	10		
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	10	10		
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	5	5		
20200100	EARTH EXCAVATION	CU YD	1147	1147		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	18	18		
20400800	FURNISHED EXCAVATION	CU YD	775	775		
20800150	TRENCH BACKFILL	CU YD	11	11		
X 213 0010	EXPLORATION TRENCH, SPECIAL	FOOT	20	20		
25000210	SEEDING, CLASS 2A	ACRE	0.5	0.5		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	40	40		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	40	40		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	40	40		
X 25100630	Erosion Control Blanket	SQ YD	2126	2126		
25200100	SODDING	SQ YD	49	49		
25200200	SUPPLEMENTAL WATERING	UNIT	1	1		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	45	45		
28000305	TEMPORARY DITCH CHECKS	FOOT	12	12		
28000500	INLET AND PIPE PROTECTION	EACH	2	2		
28000510	INLET FILTERS	EACH	11	11		
28100105	STONE RIPRAP, CLASS A3	SQ YD	18	18		
28200200	FILTER FABRIC	SQ YD	18	18		
31101100	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	121	121		
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	639	639		
35501300	HOT-MIX ASPHALT BASE COURSE, 4"	SQ YD	65	65		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	23	23		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	31	31		
42001300	PROTECTIVE COAT	SQ YD	1799	1799		

X - INDICATES SPECIAL PROVISION  
 ~ - INDICATES SPECIALTY ITEM

DESIGNED - PK	REVISED -
DRAWN - PK	REVISED -
CHECKED - RTM	REVISED -
DATE - 7/1/2010	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SHEET NO. 1 OF 3 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2625	07-00097-00-SW	DUPAGE	31	3
CONTRACT NO. 63502				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				