

PLAN	DATE
SURVEYED	BY
ALIGNMENT CHECKED	
RTM OF WAY CHECKED	
NO. _____	
PROJ. FILE NAME	

PROFILE	DATE
SURVEYED	BY
GRADES CHECKED	
RTM NOTED	
STRUCTURE NOTATIONS CHECKED	
NO. _____	

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	SFTY - 1B	SFTY - 2A	NON-PARTICIPATING
				ROADWAY	BRIDGE	ROADWAY
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	13073	13073		
42400800	DETECTABLE WARNINGS	SQ FT	43	43		
44000100	PAVEMENT REMOVAL	SQ YD	917	917		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	68	68		
44000600	SIDEWALK REMOVAL	SQ FT	190	190		
44004250	PAVED SHOULDER REMOVAL	SQ YD	200	200		
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	34	34		
50157300	PROTECTIVE SHIELD	SQ YD	120		120	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	44.9		44.9	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	6750		6750	
X ^	X5091755 PARAPET RAILING, SPECIAL	FOOT	339		339	
X	54215547 METAL END SECTIONS 12"	EACH	9	9		
	54244405 FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	1	1		
	550B0050 STORM SEWERS, CLASS B, TYPE 1 12"	FOOT	315	315		
	55100500 STORM SEWER REMOVAL 12"	FOOT	8	8		
	60207915 CATCH BASINS, TYPE C, TYPE 11V FRAME AND GRATE	EACH	8	8		
	60265700 VALVE VAULTS TO BE ADJUSTED	EACH	1	1		
	60500060 REMOVING INLETS	EACH	1	1		
	60603800 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1915	1915		
^	63100085 TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2		
X ^	63100167 TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2		
	63200310 GUARDRAIL REMOVAL	FOOT	905	905		
^	66400105 CHAIN LINK FENCE, 4'	FOOT	1420	1420		
	67100100 MOBILIZATION	L SUM	1	1		
	70100460 TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
	70100800 TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1		
	70100815 TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	L SUM	1	1		

X - INDICATES SPECIAL PROVISION
 ^ - INDICATES SPECIALTY ITEM

DESIGNED - PK	REVISED -
DRAWN - PK	REVISED -
CHECKED - RTM	REVISED -
DATE - 7/1/2010	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SHEET NO. 2 OF 3 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2625	07-00097-00-SW	DUPAGE	31	4
CONTRACT NO. 63502				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				