

PLAN	SURVEYED	DATE
NOTE BOOK	ALIGNED	BY
NO.	CHECKED	
	FILED	
	FILE NAME	

PROFILE	SURVEYED	DATE
NOTE BOOK	GRADES CHECKED	BY
NO.	BY	
	NOTED	
	SIGNATURE	NOTATIONS
	CHRG	

X - INDICATES SPECIAL PROVISION
 ^ - INDICATES SPECIALTY ITEM

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	SFTY - 1B	SFTY - 2A	NON-PARTICIPATING
				ROADWAY	BRIDGE	ROADWAY
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
^ 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2208	2208		
X ^ 78200405	GUARDRAIL MARKERS	EACH	36	36		
X ^ 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2		
X Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
X Z0019600	DUST CONTROL WATERING	UNIT	10	10		
X XX004878	MAINTENANCE OF TEMPORARY EROSION CONTROL SYSTEMS	L SUM	1	1		
X XX005221	TOPSOIL FURNISH AND PLACE (PULVERIZED) VARIABLE DEPTH	SQ YD	2126	2126		
X XX006698	TREE PROTECTION AND PRESERVATION	EACH	8	8		
X Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	102	102		
X X0322919	CLEAN EXISTING STRUCTURES	EACH	3			3
X Z0023202	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	27	27		
X Z0023204	SEDIMENT CONTROL, SILT FENCE	FOOT	1831	1831		
X Z0023206	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	183	183		
X Z0026346	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1		
X X7011015	TRAFFIC CONTROL AND PROTECTION,(EXPRESSWAYS)	L SUM	1	1		
X Z0012305	CONCRETE BRIDGE DECK SCARIFICATION, 2"	SQ YD	52		52	

SCHEDULE OF EARTH QUANTITIES			
	EARTH EXCAVATION (20200100)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (20201200)	FURNISHED EXCAVATION (20400800)
	(CU. FT.)	(CU. FT.)	(CU. FT.)
SUBTOTAL MILL ROAD			
	30,976	473	18,192
PROJECT SUBTOTAL (CU. FT.)			
	30,976	473	18,192
PROJECT SUBTOTAL (CU. YD.)			
	1,147	18	674
SHRINKAGE FACTOR ADJUSTMENT (15%)			
	-	-	x 1.15
PROJECT TOTAL (CU. YD.)			
	1,147	18	775
DENSITY FACTOR CONVERSION (2.00 TONS/CU. YD.)			
	-	x 2.00	-
PROJECT TOTAL (TONS)			
	-	36	-

DESIGNED - PK	REVISED -
DRAWN - PK	REVISED -
CHECKED - RTM	REVISED -
DATE - 7/1/2010	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SHEET NO. 3 OF 3 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2625	07-00097-00-SW	DUPAGE	31	5
CONTRACT NO. 63502				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				