CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	I000-1A	Y031-1F	Y030-1E	X281-2A	
				ROADWAY	TRAFFIC SIGNALS	LIGHTING	STRUCTURES	NON-PARTICIPATING
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	62	62				
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	18	18				
20101000	TEMPORARY FENCE	FOOT	400	400				
20101200	TREE ROOT PRUNING	EACH	10	10				
20200100	EARTH EXCAVATION	CU YD	2791	2791				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2050	2050				
20400800	FURNISHED EXCAVATION	CU YD	4499	4499				
X0326160	POROUS GRANULAR EMBANKMENT, SUBGRADE (SPECIAL)	CU YD	50	50				
20800150	TRENCH BACKFILL	CU YD	14	14				
● 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	6345	6345				
X21300 10	EXPLORATION TRENCH, SPECIAL	FOOT	100	100				
● 25000210	SEEDING, CLASS 2A	ACRE	1.4	1.4				
● 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	118	118				
● 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	118	118				
● 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	118	118				
25100630	EROSION CONTROL BLANKET	SQ YD	6345	6345				
25200200	SUPPLEMENTAL WATERING	UNIT	95	95				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	140	140				
28000305	TEMPORARY DITCH CHECKS	FOOT	96	96				
28000510	INLET FILTERS	EACH	24	24				
28100105	STONE RIPRAP, CLASS A3	SQ YD	12	12				
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	229	229				
31102000	SUB-BASE GRANULAR MATERIAL, TYPE C	CU YD	18	18				
35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	1246	1246				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	273	273				
40600300	AGGREGATE (PRIME COAT)	TON	1	1				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	2	2				
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	157	157				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	169	169				
42000506	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)	SQ YD	628	628				
42001300	PROTECTIVE COAT	SQ YD	1779	1779				
44000100	PAVEMENT REMOVAL	SQ YD	1100	1100				
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	478	478				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2256	2256				
44002207	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 1 3/4"	SQ YD	21	21				
44003100	MEDIAN REMOVAL	SQ FT	8481	8481				
44004250	PAVED SHOULDER REMOVAL	SQ YD	320	320				

● SPECIALTY ITEM