

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	I000-1A	Y031-1F	Y030-1E	X281-2A	
				ROADWAY	TRAFFIC SIGNALS	LIGHTING	STRUCTURES	NON-PARTICIPATING
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	14	14				
44200990	CLASS B PATCHES, TYPE I, 12 INCH	SQ YD	21	21				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1455	1455				
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	149	149				
48300300	PORTLAND CEMENT CONCRETE SHOULDERS 8"	SQ YD	258	258				
50102400	CONCRETE REMOVAL	CU YD	26.5				26.5	
50157300	PROTECTIVE SHIELD	SQ YD	70				70	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	10.8				10.8	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1370				1370	
52000050	PREFORMED JOINT SEAL 4"	FOOT	79				79	
54215547	METAL END SECTIONS 12"	EACH	1	1				
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	39	39				
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	23	23				
55100500	STORM SEWER REMOVAL 12"	FOOT	100	100				
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	3	3				
60107600	PIPE UNDERDRAINS 4"	FOOT	717	717				
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	46	46				
60100945	PIPE DRAINS 12"	FOOT	58	58				
60109510	PIPE UNDERDRAINS, FABRIC LINED TRENCH 4"	FOOT	100	100				
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	6	6				
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1				
60403400	GRATES, TYPE A	EACH	1	1				
60500080	REMOVING CATCH BASINS TO MAINTAIN FLOW	EACH	5	5				
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	2	2				
60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	483	483				
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1011	1011				
60619200	CONCRETE MEDIAN, TYPE SB-6.06	SQ FT	1613	1613				
60900515	CONCRETE THRUST BLOCKS	EACH	1	1				
67100100	MOBILIZATION	L SUM	1	1				
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1				
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	822	822				
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	3435	3435				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1145	1145				
● 72000100	SIGN PANEL - TYPE 1	SQ FT	24	24				
● 72000200	SIGN PANEL - TYPE 2	SQ FT	16	16				
● 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	1	1				
● 72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	1	1				

● SPECIALTY ITEM

FILE NAME =	USER NAME = djk	DESIGNED - BLG	REVISED -
...ood\sheet\2349_Sum_Quant.dgn		DRAWN - BLG	REVISED -
	PLOT SCALE = 50.0000' / IN.	CHECKED - DJK	REVISED -
	PLOT DATE = 7/7/2010	DATE - 07-07-10	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SHEET NO. 2 OF 4 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1339	09-00054-00-CH	COOK	88	5
CONTRACT NO. 63505				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT ARA-M-90031569				