

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	I000-1A	Y031-1F	Y030-1E	X281-2A	NON-PARTICIPATING
				ROADWAY	TRAFFIC SIGNALS	LIGHTING	STRUCTURES	
● 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	1	1				
● 72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	1	1				
● 72400730	RELOCATE SIGN PANEL - TYPE 3	SQ FT	60	60				
● 72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	303	303				
● 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	64	64				
● 73000100	WOOD SIGN SUPPORT	FOOT	17	17				
● 73400100	CONCRETE FOUNDATIONS	CU YD	1.4	1.4				
● 73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	2	2				
● 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	130	130				
● 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1289	1289				
● 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	880	880				
● 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	52	52				
● 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	172	172				
● 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	95	95				
● 78008230	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 6"	FOOT	916	916				
● 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	26	26				
● 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1			1		
● 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1			1		
● 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	452		452			
● 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	587			587		
● 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	183		183			
● 81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	5		5			
● 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	266		56	210		
● 81019000	CONDUIT PUSHED, 5" DIA., GALVANIZED STEEL	FOOT	60			60		
● 81030100	CONDUIT SPLICE	EACH	1		1			
● 81400100	HANDHOLE	EACH	3		3			
● 81603203	UNIT DUCT, 600V, 3-1C NO. 2, 1/C NO. 4 GROUND, (EPR-TYPE RHW) 1 1/2" DIA. POLYETHYLENE	FOOT	1510			1510		
● 81702150	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	742			742		
● 81702230	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C 500MCM	FOOT	2226			2226		
● 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2592		452	2140		
● 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	1			1		
● 84200804	REMOVAL OF POLE FOUNDATION	EACH	3			3		
● 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	3			3		
● 84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1			1		
● 84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1			1		
● 84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1			1		
● 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	3		3			
● 86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1			

● SPECIALTY ITEM

FILE NAME = ...cod\sheet\2349_Sum_Quant.dgn	USER NAME = djc	DESIGNED - BLG	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.U. RTE. 1339	SECTION 09-00054-00-CH	COUNTY COOK	TOTAL SHEETS 88	SHEET NO. 6	
PLOT SCALE = 50.0000' / IN.	CHECKED - DJK	REVISED -									
PLOT DATE = 7/23/2010	DATE - 07-07-10	REVISED -									
					SHEET NO. 3 OF 4 SHEETS	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT ARA-M-9003569					

CONTRACT NO. 63505