

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	1000-1A	Y031-1F	Y030-1E	X281-2A	
				ROADWAY	TRAFFIC SIGNALS	LIGHTING	STRUCTURES	NON-PARTICIPATING
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	267		267			
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2525		2525			
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	1		1			
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	4		4			
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	4			4		
87900200	DRILL EXISTING HANDHOLE	EACH	4		4			
88500100	INDUCTIVE LOOP DETECTOR	EACH	6		6			
88600100	DETECTOR LOOP, TYPE I	FOOT	303		303			
89500100	RELOCATE EXISTING SIGNAL HEAD	EACH	1		1			
89502205	MODIFY EXISTING CONTROLLER (SPECIAL)	EACH	3		3			
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1016		981	35		
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	66			66		
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2		2			
89502380	REMOVE EXISTING HANDHOLE	EACH	3		3			
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	2		1	1		
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	2865	2865				
Z0006000	BRIDGE DECK CONCRETE OVERLAY	SQ YD	31				31	
Z0018913	DRILL AND GROUT #8 TIE BARS	EACH	1107	1107				
A2005024	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 3" CALIPER, BALLED AND BURLAPPED	EACH	6	6				
A2005424	TREE, LIRIODENDRON TULIPIFERA (TULIP TREE), 3" CALIPER, BALLED AND BURLAPPED	EACH	7	7				
Z0018911	DRILL AND GROUT #6 TIE BARS	EACH	365	365				
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51	51				
X0322708	REMOVE EXISTING STREET LIGHTING EQUIPMENT	EACH	1			1		
Z0033090	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	2650		2650			
Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	3			3		
X0323797	PAINT NEW TRAFFIC SIGNAL POST	EACH	1		1			
Z0023204	SEDIMENT CONTROL, SILT FENCE	FOOT	1675	1675				
Z0023206	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	168	168				
Z0026346	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1				
Z0033044	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 1	EACH	1		1			
X6065740	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	SQ FT	2061	2061				
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1			1		
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1				
X8250110	LIGHTING CONTROLLER, RADIO CONTROL, DUPLEX CONSOLE TYPE, WITH SCADA	EACH	1			1		
X8360360	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 10" X 8"	EACH	3			3		
X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	2696		2696			
X8950700	REMOVE TEMPORARY INTERCONNECT	L SUM	1		1			
XX006862	TEMPORARY VIDEO DETECTION	L SUM	1		1			

● SPECIALTY ITEM

FILE NAME = ...\\ced\sheet\2349_Sum_Quant.dgn

USER NAME = djc
 PLOT SCALE = 50.0000' / IN.
 PLOT DATE = 7/7/2010

DESIGNED - BLG
 DRAWN - BLG
 CHECKED - DJK
 DATE - 07-07-10

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SHEET NO. 4 OF 4 SHEETS

F.A.U. RTE. 1339	SECTION 09-00054-00-CH	COUNTY COOK	TOTAL SHEETS 88	SHEET NO. 7
CONTRACT NO. 63505				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT ARA-M-9003569				