

| CODE NO | PAY ITEM | UNIT | ROADWAY (000) |
|-----------|--|--------|---------------|
| 20201200 | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL | CU YD | 444 |
| Z0042002 | POROUS GRANULAR EMBANKMENT, SUBGRADE | CU YD | 444 |
| 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 494 |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 8 |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 8 |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 8 |
| 25200110 | SODDING, SALT TOLERANT | SQ YD | 494 |
| 35101500 | AGGREGATE BASE COURSE, TYPE B | CU YD | 7 |
| 35501316 | HOT-MIX ASPHALT BASE COURSE, 8" | SQ YD | 8 |
| 40201000 | AGGREGATE FOR TEMPORARY ACCESS | TON | 50 |
| 40600100 | BITUMINOUS MATERIALS (PRIME COAT) | GALLON | 10719 |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 214 |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 27 |
| X4060 826 | POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50 | TON | 2,251 |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 2 |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 172 |
| 40601005 | HOT-MIX ASPHALT REPLACEMENT OVER PATCHES | TON | 1025 |
| 40603310 | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 | TON | 1 |
| 40603595 | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90 | TON | 5228 |
| 42300400 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH | SQ YD | 8 |
| 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH | SQ FT | 1,115 |
| 42400800 | DETECTABLE WARNINGS | SQ FT | 32 |
| 44000159 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2" | SQ YD | 53,419 |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQ YD | 16 |
| 44000600 | SIDEWALK REMOVAL | SQ FT | 1,115 |
| Z0004562 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 1,764 |
| 44002210 | HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/2" | SQ YD | 6650 |
| 44201773 | CLASS D PATCHES, TYPE I, 11 INCH | SQ YD | 1,330 |
| 44201777 | CLASS D PATCHES, TYPE II, 11 INCH | SQ YD | 1,330 |
| 44201781 | CLASS D PATCHES, TYPE III, 11 INCH | SQ YD | 1,330 |
| 44201783 | CLASS D PATCHES, TYPE IV, 11 INCH | SQ YD | 1,330 |
| 60300310 | FRAMES AND LIDS TO BE ADJUSTED (SPECIAL) | EACH | 33 |

* = SPECIALTY ITEM
 Δ = Y080

| CODE NO | PAY ITEM | UNIT | ROADWAY (000) |
|------------|--|--------|---------------|
| 67100100 | MOBILIZATION | L SUM | 1 |
| 70102625 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701806 | L SUM | 1 |
| 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 | L SUM | 1 |
| 70102640 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801 | L SUM | 1 |
| 70106800 | CHANGEABLE MESSAGE SIGN | CAL MO | 2 |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 2860 |
| 70300210 | TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 436 |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 13931 |
| 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 8667 |
| 70300260 | TEMPORARY PAVEMENT MARKING - LINE 12" | FOOT | 1686 |
| 70300280 | TEMPORARY PAVEMENT MARKING - LINE 24" | FOOT | 317 |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 11732 |
| * 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 436 |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 13931 |
| * 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 8667 |
| * 78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 1686 |
| * 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 317 |
| 88600600 | DETECTOR LOOP REPLACEMENT | FOOT | 918 |
| Z0030850 | TEMPORARY INFORMATION SIGNING | SQ FT | 51 |
| Z0017400 | DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED | EACH | 22 |
| Δ Z0076800 | TRAINEES | HOURL | 500 |

FILE NAME = #FILES



| | | |
|----------------------|-----------------|-----------|
| USER NAME = #USER# | DESIGNED - Y00 | REVISED - |
| | DRAWN - Y00 | REVISED - |
| PLOT SCALE = #SCALE# | CHECKED - DDL | REVISED - |
| PLOT DATE = #DATE# | DATE - 7/6/2010 | REVISED - |

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

NTS SHEET NO. 3 OF SHEETS STA. 48+87 TO STA. 152+78

| | | | | |
|---|----------------|--------|--------------|-----------|
| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 2552 | 10-00148-00-RS | DUPAGE | 24 | 3 |
| CONTRACT NO. 63506 | | | | |
| FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT | | | | |