SCHEDULE OF QUANTITIES

28000400 PERIMETER EROSION BARRIER

FOOT	LOCATION				OFFSET (ft)	REMARKS
	IL 76					
295	Rt. Sta.	233+50.0	TO	235+82.0		
	Orth Rd					
315	Lt. Sta.	519+00.0	TO	522+00.0		
610 TOTAL						

28000500 INLET AND PIPE PROTECTION

EACH	LOCATION		OFFSET (ft)	REMARKS
	IL 76			
1	Rt Sta.	229+51.0	38.32	At Entrance.
1	Rt Sta.	243+10.0	38.27	At Entrance.
1	Rt Sta.	248+50.0		
	Orth Rd			
1	Lt. Sta.	511+62	26.26	At Entrance.
1	Lt. Sta.	519+19.5	31.28	At Entrance.
1	Lt. Sta.	517+50.0	26.13	At Entrance.
1	Rt Sta.	520+14.0	26.20	At Entrance.
7 TOTAL				

542D0220 PIPE CULVERTS, CLASS D, TYPE 1 15"

FOOT	LOCATION		OFFSET (ft)	REMARKS
	IL 76			
50	Rt. Sta.	229+48.9	37.94	PE
52	Rt. Sta.	243+34.5	37.87	FE
40	Rt. Sta.	248+50.0		
	Orth Rd			
60	Lt. Sta.	511+42.0	25	PE
48	Lt. Sta.	517+05.6	33.84	FE
60	Rt. Sta.	520+36.5	26.21	FE
310 TOTAL				

542D0229 PIPE CULVERTS, CLASS D, TYPE 1 24"

FOOT	LOCATION		OFFSET (ft)	REMARKS
	Orth Rd			
41	Lt. & Rt. Sta	517+50.0	20' L to 21' R	

5421D015 PIPE CULVERTS, CLASS D, TYPE 1 15" (TEMPORARY)

FOOT	LOCATION		OFFSET (ft)	REMARKS
	Orth Rd			
50	Rt. Sta	229+48.0	20' L to 21' R	
50	Rt. Sta	243+34.0		
100 TOTAL				

5421D030 PIPE CULVERTS, CLASS D, TYPE 1 30"

FOOT	LOCATION		OFFSET (ft)	REMARKS
	Orth Rd			
12	Rt. Sta	235+78.0	20' L to 21' R	
12	Rt. Sta	237+07.0	20' L to 21' R	
24 TOTAL				

54213450 END SECTIONS 15"

EACH	LOCATION		OFFSET (ft)	REMARKS
	IL 76			
2	Rt. Sta.	229+48.9	37.94	PE
2	Rt. Sta.	243+34.5	37.87	FE
2	Rt. Sta.	248+50.0	35.35	
	Orth Rd			
2	Lt. Sta.	511+42.0	25	PE
2	Lt. Sta.	517+05.6	33.84	FE
2	Rt. Sta.	520+36.5	26.21	FE
12 TOTAL				

54213459 END SECTIONS 24"

EACH	LOCATION		OFFSET (ft)	REMARKS
	IL 76			
2	Lt. & Rt. Sta	517+50.0	20' L to 21' R	

60608600 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06

FOOT	LOCATION	OFFSET (ft)	REMARKS
	IL 76/ORTH ROAD INTERSECION		
22	NE ISLAND	Lt	
34	NW ISLAND	Rt	
23	SW ISLAND	Lt	
79 TOTAL			

60610400 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24

FOOT	LOCATION	OFFSET (ft)	REMARKS
	IL 76/ORTH ROAD INTERSECION		
33	NE ISLAND		
57	NW ISLAND		
34	SW ISLAND		
124 TOTAL			

60618300 CONCRETE MEDIAN SURFACE , 4 INCH

SQ FT	LOCATION	OFFSET (ft)	REMARKS
	IL 76/ORTH ROAD INTERSECION		
100	NE ISLAND	Lt	
230	NW ISLAND	Rt	
100	SW ISLAND	Lt	
430 TOTAL			

Note: See plan sheets for offset.

FILE NAME = c:\pw_work\pwidot\goffjl\dms85448\d0898	USER NAME = goffjl	DESIGNED -	REVISED -
spl.dgn		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = Mon Mar 22 10:40:14 2010	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
754	101M-1	BOONE	74	13
		CONTRACT NO. 64E34		
		ILLINOIS FED. AID PROJECT		