

SCHEDULE OF QUANTITIES

78000100 THEMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS						
SQ FT		LOCATION		OFFSET (ft)	REMARKS	
<u>WHITE</u>		<u>IL 76</u>				
15.6		Sta.	233+35.5		Lt. Turn Arrow	
15.6		Sta.	234+10.6		Lt. Turn Arrow	
15.6		Sta.	234+85.6		Lt. Turn Arrow	
15.6		Sta.	235+60.6		Lt. Turn Arrow	
15.6		Sta.	237+19.0		Lt. Turn Arrow	
15.6		Sta.	237+94.0		Lt. Turn Arrow	
15.6		Sta.	238+69.0		Lt. Turn Arrow	
15.6		Sta.	239+44.0		Lt. Turn Arrow	
124.8	TOTAL					

78000200 THEMOPLASTIC PAVEMENT MARKING - LINE 4"						
FOOT		LOCATION		OFFSET (ft)	REMARKS	
<u>WHITE</u>		<u>IL 76</u>				
1297		Lt. Sta.	223+39.3	TO 236+36.5	White Edge line Left	
1309		Lt. Sta.	236+70.4	TO 249+79.3	White Edge line Left	
	4970	L & R Sta.	223+39.3	TO 235+81.8	Median	
1278		Rt. Sta.	223+39.3	TO 236+17.4	White Edge line Right	
1336		Rt. Sta.	236+43.4	TO 249+79.3	White Edge line Right	
	3320	L & R Sta.	236+97.8	TO 245+27.8	Median	
		<u>Orth Rd</u>				
511		Rt. Sta.	508+70.0	TO 513+81.3	White Edge line Right	
421		Lt. Sta.	508+70.0	TO 512+90.8	White Edge line Left	
410		Rt. Sta.	517+40.0	TO 521+50.0	White Edge line Right	
437		Lt. Sta.	517+13.0	TO 521+50.0	White Edge line Left	
	1162	Lt. & Rt. Sta	508+70.0	TO 514+51.0	Double CL	
	1012	Lt. & Rt. Sta	516+44.0	TO 521+50.0	Double CL	
6999	10464					
	17463	TOTAL				

Note: Start and End edge lines as the stations used in staging plans.

78000500 THEMOPLASTIC PAVEMENT MARKING - LINE 8"						
FOOT		LOCATION		OFFSET (ft)	REMARKS	
<u>WHITE</u>		<u>IL 76</u>				
76		Lt. & Rt. Sta	230+91.7	TO 233+16.8	6.33 Rt	Turkey Tracks
265		Lt. & Rt. Sta	233+16.8	TO 235+81.8	6.33 Rt	LT Turn Lane
265		Lt. & Rt. Sta	236+97.8	TO 239+62.9	6.33 Lt	LT Turn Lane
76		Lt. & Rt. Sta	239+62.9	TO 241+87.6	6.33 Lt	Turkey Tracks
		<u>Orth Rd</u>				
198		Lt. Sta.	514+15.3	TO 514+75.9		Island
115		Rt. Sta.	514+44.0	TO 514+75.3		Island
113		Lt. Sta.	516+19.0	TO 516+50.4		Island
1108	TOTAL					

78000600 THEMOPLASTIC PAVEMENT MARKING - LINE 12"						
FOOT		LOCATION		OFFSET (ft)	REMARKS	
<u>WHITE</u>		<u>IL 76</u>				
	155	Lt. & Rt. Sta	227+70.4	TO 233+06.0	Median Diagonals	
	155	Lt. & Rt. Sta	239+81.0	TO 244+90.0	Median Diagonals	
		<u>Orth Rd</u>				
149		Lt. Sta.	514+15.3	TO 514+75.9	Island Diagonals	
55		Rt. Sta.	514+44.0	TO 514+75.3	Island Diagonals	
55		Lt. Sta.	516+19.0	TO 516+50.4	Island Diagonals	
259	310					
	569	TOTAL				

78000650 THEMOPLASTIC PAVEMENT MARKING - LINE 24"						
FOOT		LOCATION		OFFSET (ft)	REMARKS	
<u>Orth Rd</u>		<u>IL 76</u>				
18		Rt. Sta.	514+47.0	TO 514+60.0	23 Rt	Stop Bar Rt. Turn Lane
12		Rt. Sta.	514+51.0			Stop Bar
18		Lt. Sta.	516+32.9	TO 516+45.3	25 Lt	Stop Bar Rt. Turn Lane
12		Lt. Sta.	516+44.0			Stop Bar
60	TOTAL					

78100100 RAISED REFLECTIVE PAVEMENT MARKERS						
EACH		LOCATION		OFFSET (ft)	REMARKS	
<u>IL 76</u>		<u>IL 76</u>				
58		Lt. & Rt. Sta	227+51.8	TO 235+81.8	2 Way Amber	
14		Rt. Sta.	233+16.8	TO 235+81.8	1 Way Crystal	
62		Lt. & Rt. Sta	236+97.8	TO 245+27.8	2 Way Amber	
14		Lt. Sta.	236+97.8	TO 239+62.8	1 Way Crystal	
148	TOTAL					

78300100 PAVEMENT MARKING REMOVAL						
SQ FT		LOCATION		OFFSET (ft)	REMARKS	
<u>WHITE</u>		<u>IL 76</u>				
1758		Lt. & Rt. Sta	223+39.3	TO 249+79.3	Edge	
	1758	Lt. Sta.	223+39.3	TO 249+79.3	Edge-DBL	
3517	TOTAL	Note: Stage I removal of existing pavement marking.				

81603000 UNIT DUCT. 600V. 2-1C NO.8. 1/C NO.8 GROUND. (XLP-TYPE)						
FOOT		LOCATION		OFFSET (ft)	REMARKS	
<u>IL 76</u>		<u>IL 76/ORTH ROAD INTERSECCION</u>				
75		SW QUARDANT				

81900200 TRENCH AND BACKFILL FOR ELECTRICAL WORK						
FOOT		LOCATION		OFFSET (ft)	REMARKS	
<u>IL 76</u>		<u>IL 76/ORTH ROAD INTERSECCION</u>				
62		SW QUARDANT				

83600100 LIGHT POLE FOUNDATION						
EACH		LOCATION		OFFSET (ft)	REMARKS	
<u>IL 76</u>		<u>IL 76/ORTH ROAD INTERSECCION</u>				
1		SW QUARDANT				