

SCHEDULE OF QUANTITIES

20400800 FURNISHED EXCAVATION
 LOCATION
 STA 755+34 TO 756+86 LT & RT

CU YD
 11.00
 TOTAL 11

21101615 TOPSOIL FURNISH AND PLACE, 4"
 LOCATION
 STA 755+34 TO 756+86 LT & RT

SQ YD
 640.00
 TOTAL 640

25100630 EROSION CONTROL BLANKET
 LOCATION
 STA 755+34 TO 756+86 LT
 STA 755+34 TO 756+86 RT

SQ YD
 368.00
 361.00
 TOTAL 729

25100900 TURF REINFORCEMENT MAT
 LOCATION
 STA 756+10 RT

SQ YD
 52
 TOTAL 52

28000300 TEMPORARY DITCH CHECKS
 LOCATION
 STA 755+75 LT & RT
 STA 756+00 LT & RT
 STA 756+25 LT & RT
 STA 756+50 LT & RT

FOOT
 20
 20
 20
 20
 TOTAL 80

28000400 PERIMETER EROSION BARRIER
 LOCATION
 STA 755+34 TO 756+86 LT
 STA 755+34 TO 756+86 RT

FOOT
 185
 200
 TOTAL 385

28000500 INLET AND PIPE PROTECTION
 LOCATION
 STA 756+10 RT

EACH
 1
 TOTAL 1

28100107 STONE RIPRAP, CLASS A4
 LOCATION
 STA 756+10 RT 15' X 20'

SQ YD
 34
 TOTAL 34

28200200 FILTER FABRIC
 LOCATION
 STA 756+10 RT 15' X 20'

SQ YD
 34
 TOTAL 34

44201383 CLASS C PATCHES, TYPE IV, 12 INCH
 LOCATION
 STA 755+92.19 TO 756+27.19

SQ YD
 94
 TOTAL 94

48101500 AGGREGATE SHOULDERS, TYPE B 6"
 LOCATION
 STA 755+34 TO 756+86 LT & RT

SQ YD
 150
 TOTAL 150

50100300 REMOVAL OF EXISTING STRUCTURES NO. 1
 LOCATION
 STA 756+10

EACH
 1
 TOTAL 1

51500100 NAME PLATES
 LOCATION
 STA 756+10

EACH
 1
 TOTAL 1

542A1081 PIPE CULVERTS, CLASS A, TYPE 2 36"
 LOCATION
 STA 756+10

FOOT
 110
 TOTAL 110

54213681 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"
 LOCATION
 STA 756+10 LT & RT

EACH
 4
 TOTAL 4

5421D018 PIPE CULVERTS, CLASS D, TYPE 1, 18" (TEMPORARY)
 LOCATION
 STA 756+10 RT 2 PIPES AT 18' EACH

FOOT
 36
 TOTAL 36

63500105 DELINEATORS
 LOCATION
 STA 756+10 LT & RT

EACH
 2
 TOTAL 2

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY-MARKERS
 LOCATION

STA 755+30.00 33' LT & R
 STA 755+95.00 75' LT
 STA 755+95.00 70' RT
 STA 756+25.00 75' LT
 STA 756+25.00 70' LT
 STA 756+85.00 33' LT & RT

EACH
 2
 1
 1
 1
 1
 2
 TOTAL 8

66700305 PERMANENT SURVEY MARKERS, TYPE II
 LOCATION
 TO BE DETERMINED BY ENGINEER

EACH
 1
 TOTAL 1

78001110 PAINT PAVEMENT MARKING - LINE 4"
 LOCATION
 STA 755+34 TO 756+86 WHITE EOP (2 Apl.)
 STA 755+34 TO 756+86 YELLOW SKIP DASH (2 Apl.)

FOOT
 608
 80
 TOTAL 688

FILE NAME =	USER NAME = cushmanbw	DESIGNED -	REVISED -
c:\pwork\pwork\cushmanbw\0149475\029903-sht-schedule.dgn		DRAWN -	REVISED -
PLOT SCALE = 50.0000' / 1"		CHECKED -	REVISED -
PLOT DATE = Thu Jun 24 06:38:20 2010		DATE -	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	157-1	WHITESIDE	17	6
CONTRACT NO. 64F35			ILLINOIS FED. AID PROJECT	