

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNITS	URBAN TOTAL QTY.	90% FED 10% STATE	90% FED 10% STATE	90% FED 5% STATE 5% CO	90% FED 10% STATE	100% CO	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE
				ROADWAY HMA I000-2A	ROADWAY CONCRETE J000-2A	SIGNAL ITEMS Y030-1E	LIGHTING Y030-1E	DIFF. OF ULT. VS. INT. I000-2A	BRIDGE BRISBIN X231-2A	BRIDGE RAMP B X081-2A	BRIDGE RAMP C X081-2A
42001300	PROTECTIVE COAT	SQ YD	68,484		68,484						
44000100	PAVEMENT REMOVAL	SQ YD	5,011		5,011						
<del>44000198</del>	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	5,089	5,089							
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	351		351						
<del>X4401980</del>	CONCRETE BARRIER REMOVAL	FOOT	430		430						
<del>X4402005</del>	ISLAND REMOVAL	SQ FT	248		248						
44004000	PAVED DITCH REMOVAL	FOOT	67		67						
44004250	<del>PAVED</del> SHOULDER REMOVAL	SQ YD	2,045		2,045						
44005000	STABILIZED SHOULDER REMOVAL	SQ YD	5,570	5,570							
44213200	SAW CUTS	FOOT	1,941		1,941						
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	5,396		5,271			125			
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	3,810	3,370				440			
48300505	PORTLAND CEMENT CONCRETE SHOULDERS 10 1/4"	SQ YD	14,793		14,793						
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1					1			
50102400	CONCRETE REMOVAL	CU YD	8.8		8						0.8
50104400	CONCRETE HEADWALL REMOVAL	EACH	9		9						
50105220	PIPE CULVERT REMOVAL	FOOT	573		573						
50157300	PROTECTIVE SHIELD	SQ YD	900					900			
50200100	STRUCTURE EXCAVATION	CU YD	373					360	3		10
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	2				2				
50300225	CONCRETE STRUCTURES	CU YD	679.3		10			558.1	59.2		52.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,355.4					872.9	247.3		235.2
50300260	BRIDGE DECK GROOVING	SQ YD	3,228					2,315	477		436
50300280	CONCRETE ENCASEMENT	CU YD	38.2					28.4	5.0		4.8
50300300	PROTECTIVE COAT	SQ YD	4,197					2,979	621		597
50400735	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 63"	FOOT	611								611
50400745	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 72"	FOOT	661							661	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1					1			
50500505	STUD SHEAR CONNECTORS	EACH	7,740					7,740			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	397,320		1,800			284,670	58,390		52,460
50800515	BAR SPLICERS	EACH	314					196	54		64
51100100	SLOPE WALL 4 INCH	SQ YD	800					800			
51201600	FURNISHING STEEL PILES HP 12X53	FOOT	220								220
51201610	FURNISHING STEEL PILES HP 12X63	FOOT	246							246	
51201900	FURNISHING STEEL PILES HP 14X89	FOOT	1,612					1,612			
51202305	DRIVING PILES	FOOT	2,078					1,612	246		220
51203600	TEST PILE STEEL HP 12X53	EACH	1								1
51203610	TEST PILE STEEL HP12X63	EACH	2						2		
51203900	TEST PILE STEEL HP14X89	EACH	2					2			
51204650	PILE SHOES	EACH	82					54	14		14
<del>20026407</del>	TEMPORARY SHEET PILING	SQ FT	1,850								1,850
51500100	NAME PLATES	EACH	3					1	1		1
52000110	PERFORMED JOINT STRIP SEAL	FOOT	201					201			
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	20					20			
52100520	ANCHOR BOLT, 1"	EACH	40					40			
52100530	ANCHOR BOLT, 1 1/4"	EACH	20					20			
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	131	79	52						

\* SPECIALTY ITEM

FILE NAME = t:\11812\CADD Sheets\0366408-sht-500.dgn	USER NAME = .USER.	DESIGNED - CGC	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - CGC	REVISED -		SCALE: NONE SHEET NO. 4 OF 351 SHEETS STA. TO STA.				(32,47-4) HBK-4 & G(N)	GRUNDY	351	4	
		CHECKED - JPW	REVISED -						CONTRACT NO. 66408				
		DATE - 5/21/2010	REVISED -						ILLINOIS FED. AID PROJECT				