

ITEM 35501311 HOT-MIX ASPHALT BASE COURSE, 6 3/4"	
LOCATION STATION TO STATION	AREA (SQ YD)
NORTH ROAD	
00+14.92 TO 09+50.67	2850
SERVICE DRIVE	
00+17.56 TO 00+59.13	166
TOTAL	3016

ITEM 40200100 AGGREGATE SURFACE COURSE, TYPE A	
LOCATION STATION TO STATION	WEIGHT (TON)
SERVICE DRIVE	
00+59.13 TO 17+66.96	2010
TOTAL	2010

ITEM 40600400 MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	
LOCATION STATION TO STATION	AREA (SQ YD)
US ROUTE 6	
189+74.73 TO 200+36.59	0.9
207+14.31 TO 215+03.29	0.6
TOTAL	1.5

ITEM 40603090 HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	
LOCATION STATION TO STATION	TON
US ROUTE 6	
190+00.00	6
191+00.00	16
192+00.00	24
193+00.00	31
194+00.00	33
195+00.00	28
196+00.00	25
197+00.00	32
198+00.00	39
199+00.00	27
200+00.00	5
200+36.59	
207+14.40	25
208+00.00	31
209+00.00	34
210+00.00	16
210+50.00	16
211+00.00	30
212+00.00	16
212+70.73	16
214+00.00	9
215+00.00	
TOTAL	459

ITEM 40600100 BITUMINOUS MATERIALS (PRIME COAT)	
LOCATION STATION TO STATION	VOL (GAL)
BRISBIN ROAD	
87+53.10 TO 96+08.10	1708
87+53.10 TO 96+08.10	633
96+08.10 TO 98+47.65	896
99+63.22 TO 113+37.69	5158
116+62.15 TO 130+30.33	3439
US ROUTE 6	
189+74.73 TO 200+36.59	1195
189+74.73 TO 200+36.59	234
207+14.40 TO 215+09.62	931
207+14.40 TO 215+09.62	242
RAMP A	
100+00.00 TO 117+12.00	1564
RAMP B	
200+46.56 TO 214+82.00	1296
216+54.02 TO 232+50.12	1089
RAMP C	
300+00.00 TO 307+71.94	664
309+35.44 TO 317+58.57	1170
RAMP D	
400+48.94 TO 428+77.79	2179
I-80	
1359+54.64 TO 1372+08.41	78
1361+03.89 TO 1377+44.85	103
1392+45.64 TO 1397+53.31	32
1394+90.18 TO 1398+09.88	356
1396+95.50 TO 1402+22.00	33
1417+34.57 TO 1433+69.74	102
1425+20.44 TO 1432+97.86	49
NORTH RD	
00+84.40 TO 09+50.67	867
TOTAL	24018

ITEM 40201000 AGGREGATE FOR TEMPORARY ACCESS	
LOCATION STATION	TON
US ROUTE 6	
210+00.00 RT	15.19
BRISBIN ROAD	
102+00.00 RT	15.19
122+00.00 LT	15.19
127+00.00 RT	15.19
NORTH ROAD	
02+00.00 RT	15.19
08+00.00 LT	15.19
TOTAL	91

ITEM 40600845 POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90	
LOCATION STATION TO STATION	TON
US ROUTE 6	
189+74.73 TO 200+36.59	126
207+14.31 TO 215+03.29	88
TOTAL	214

ITEM 40603310 HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	
LOCATION STATION TO STATION	TON
NORTH ROAD	
00+14.92 TO 09+50.67	312
SERVICE DRIVE	
00+17.56 TO 00+59.13	18
TOTAL	330

ITEM 40600300 AGGREGATE (PRIME COAT)	
LOCATION STATION TO STATION	TON
BRISBIN ROAD	
87+53.10 TO 96+08.10	9
96+08.10 TO 98+47.65	5
99+63.22 TO 113+37.69	28
116+62.15 TO 130+30.33	18
US ROUTE 6	
189+74.73 TO 200+36.59	12
200+36.59 TO 207+14.40	16
207+14.40 TO 215+09.62	9
RAMP A	
100+00.00 TO 117+12.00	8
RAMP B	
200+46.56 TO 214+82.00	7
216+54.02 TO 232+50.12	6
RAMP C	
300+00.00 TO 307+71.94	4
309+35.44 TO 317+58.57	6
RAMP D	
400+48.94 TO 428+77.79	12
I-80	
1359+54.64 TO 1372+08.41	0
1361+03.89 TO 1377+44.85	1
1392+45.64 TO 1397+53.31	0
1394+90.18 TO 1398+09.88	2
1396+95.50 TO 1402+22.00	0
1417+34.57 TO 1433+69.74	1
1425+20.44 TO 1432+97.86	0
TOTAL	144

ITEM 40600895 CONSTRUCTING TEST STRIP	
LOCATION STATION TO STATION	EACH
	7
TOTAL	7

ITEM 40603545 POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	
LOCATION STATION TO STATION	TON
US ROUTE 6	
189+74.73 TO 200+36.59	252
207+14.31 TO 215+03.29	176
TOTAL	428

ITEM 40600115 POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	
LOCATION STATION TO STATION	VOL (GAL)
BRISBIN ROAD	
87+53.10 TO 96+08.10	752
US ROUTE 6	
189+74.73 TO 200+36.59	574
207+14.40 TO 215+09.62	447
TOTAL	1773

ITEM 40603085 HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	
LOCATION STATION TO STATION	TON
STAGE 1	
US ROUTE 6	
182+80.00 TO 198+12.00	801
209+64.00 TO 222+20.00	628
BRISBIN ROAD	
83+53.00 TO 98+41.00	1044
STAGE 2	
US ROUTE 6	
182+20.00 TO 200+37.00	1373
207+14.00 TO 210+35.00	161
210+65.00 TO 221+84.00	658
BRISBIN ROAD	
83+53.00 TO 96+08.00	868
98+68.00 TO 98+92.00	23
TOTAL	5555

ITEM 40702011 HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 16 1/2"	
LOCATION STATION TO STATION	AREA (SQ YD)
BRISBIN ROAD	
87+53.10 TO 96+08.10	3954
US ROUTE 6	
189+74.73 TO 200+36.59	587
189+74.73 TO 200+36.59	873
207+14.41 TO 215+09.62	883
207+14.41 TO 215+09.62	624
TOTAL	6921