

ITEM 42000506 PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)	
LOCATION STATION TO STATION	AREA (SQ YD)
BRISBIN ROAD	
96+08.10 TO 98+51.32	2255
99+59.57 TO 113+64.81	11213
116+35.04 TO 130+30.33	7501
RAMP A	
100+00.00 TO 117+15.58	3706
RAMP B	
200+42.83 TO 232+50.12	5875
RAMP C	
300+00.00 TO 317+61.68	4785
RAMP D	
400+46.05 TO 428+77.79	5100
US ROUTE 6	
200+36.59 TO 207+14.40	7139
TOTAL	47574

ITEM 44000100 PAVEMENT REMOVAL	
LOCATION STATION TO STATION	AREA (SQ YD)
US ROUTE 6	
200+36.59 TO 207+14.40	3026
EX NORTH ROAD	
01+33.55 TO 09+53.89	1985
TOTAL	5011

ITEM 44002805 ISLAND REMOVAL	
LOCATION	LENGTH (FT)
BRISBIN & US ROUTE 6	
	248
TOTAL	248

ITEM 44004500 STABILIZED SHOULDER REMOVAL	
LOCATION STATION TO STATION	AREA (SQ YD)
US ROUTE 6	
189+74.73 TO 203+68.40	1478
189+74.73 TO 203+35.29	1512
203+56.39 TO 215+09.62	1266
203+95.67 TO 215+09.62	1314
TOTAL	5570

ITEM 42001300 PROTECTIVE COAT	
LOCATION STATION TO STATION	AREA (SQ YD)
BRISBIN ROAD	
96+07.93 TO 98+48.68	2353
99+62.21 TO 113+37.69	13466
116+62.15 TO 130+30.33	10813
RAMP A	
100+00.00 TO 117+13.00	5255
RAMP B	
200+45.52 TO 215+18.44	4792
216+52.71 TO 232+50.12	3786
RAMP C	
300+00.00 TO 308+08.09	2553
309+34.38 TO 317+56.97	3673
RAMP D	
400+53.51 TO 428+77.79	7663
I-80	
1359+54.64 TO 1372+08.41	698
1361+03.89 TO 1377+44.85	1125
1392+45.64 TO 1397+53.31	832
1394+90.18 TO 1398+09.88	949
1396+95.50 TO 1402+22.00	847
1417+34.57 TO 1433+69.74	1085
1425+20.44 TO 1436+61.07	741
US 6	
200+36.59 TO 207+14.40	7853
TOTAL	68484

ITEM 44000198 HOT-MIX ASPHALT REMOVAL, VARIABLE DEPTH	
LOCATION STATION TO STATION	AREA (SQ YD)
US ROUTE 6	
189+74.73 TO 200+36.59	2996
207+14.31 TO 215+03.29	2093
TOTAL	5089

ITEM 44004000 PAVED DITCH REMOVAL	
LOCATION STATION TO STATION	LENGTH (FT)
BRISBIN ROAD	
I-80	
1397+89.23 TO 1398+53.89	67
TOTAL	67

ITEM 44213200 SAW CUTS	
LOCATION STATION TO STATION	LENGTH (FT)
BRISBIN ROAD	
96+08.10	24
130+30.33	26
I-80	
1392+45.47 TO 1397+01.84	462
1394+90.18 TO 1398+09.89	693
1397+06.03 TO 1401+75.23	475
1409+25.74 TO 1410+74.68	169
US ROUTE 6	
200+36.59	33
207+14.40	32
NORTH ROAD	
09+50.67	27
TOTAL	1941

ITEM 44000200 DRIVEWAY PAVEMENT REMOVAL	
LOCATION STATION	AREA (SQ YD)
BRISBIN ROAD	
101+74.87	351
TOTAL	351

ITEM 44004510 PORTLAND CEMENT CONCRETE SHOULDER REMOVAL	
LOCATION STATION TO STATION	AREA (SQ YD)
I-80	
1393+80.00 TO 1398+09.89	1276
1434+11.79 TO 1437+03.06	351
1409+24.72 TO 1434+47.02	418
TOTAL	2045

ITEM 48101500 AGGREGATE SHOULDERS, TYPE B 6"	
LOCATION STATION TO STATION	AREA (SQ YD)
RAMP A	
100+00.00 TO 116+36.11	416
106+59.67 TO 116+72.81	257
RAMP B	
200+99.12 TO 211+95.81	269
201+34.43 TO 212+11.83	271
216+22.07 TO 232+50.12	422
216+29.11 TO 219+61.84	81
RAMP C	
300+00.00 TO 303+62.50	96
309+19.38 TO 316+91.17	189
309+23.97 TO 317+27.41	204
RAMP D	
401+44.59 TO 416+04.82	324
401+71.58 TO 428+77.79	689
I-80	
1359+54.64 TO 1371+62.33	302
1361+03.89 TO 1377+16.43	404
1417+56.72 TO 1433+69.74	404
1425+90.30 TO 1433+22.57	183
NORTH ROAD	
00+54.55 TO 09+56.08	455
01+14.12 TO 09+45.27	430
TOTAL	5396

ITEM 44001980 CONCRETE BARRIER REMOVAL	
LOCATION STATION TO STATION	LENGTH (FT)
I-80	
1393+80.00 TO 1398+09.98	430
TOTAL	430

• FAI 80 & FAS 297 / FAU 392