

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BEAM 7

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. S. Abut.	113+83.42	12.50	569.85	569.85
CL Brg. S. Abut.	113+87.58	12.50	569.88	569.88
A	113+97.58	12.50	569.95	570.01
B	114+07.58	12.50	570.00	570.12
C	114+17.58	12.50	570.06	570.21
D	114+27.58	12.50	570.10	570.28
E	114+37.58	12.50	570.14	570.33
F	114+47.58	12.50	570.18	570.35
G	114+57.58	12.50	570.21	570.36
H	114+67.58	12.50	570.23	570.35
I	114+77.58	12.50	570.25	570.32
J	114+87.58	12.50	570.26	570.30
K	114+97.58	12.50	570.26	570.27
CL Brg. Pier	115+09.08	12.50	570.26	570.26
L	115+19.08	12.50	570.25	570.26
M	115+29.08	12.50	570.23	570.27
N	115+39.08	12.50	570.21	570.29
O	115+49.08	12.50	570.19	570.30
P	115+59.08	12.50	570.16	570.30
Q	115+69.08	12.50	570.12	570.29
R	115+79.08	12.50	570.07	570.26
S	115+89.08	12.50	570.02	570.20
T	115+99.08	12.50	569.97	570.12
U	116+09.08	12.50	569.90	570.02
V	116+19.08	12.50	569.83	569.90
CL Brg. N. Abut.	116+30.58	12.50	569.75	569.75
Bk. N. Abut.	116+34.74	12.50	569.71	569.71

BEAM 8

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. S. Abut.	113+89.53	20.83	569.72	569.72
CL Brg. S. Abut.	113+93.69	20.83	569.75	569.75
A	114+03.69	20.83	569.81	569.87
B	114+13.69	20.83	569.86	569.98
C	114+23.69	20.83	569.91	570.06
D	114+33.69	20.83	569.95	570.13
E	114+43.69	20.83	569.99	570.18
F	114+53.69	20.83	570.02	570.20
G	114+63.69	20.83	570.05	570.20
H	114+73.69	20.83	570.07	570.18
I	114+83.69	20.83	570.08	570.16
J	114+93.69	20.83	570.09	570.13
K	115+03.69	20.83	570.09	570.10
CL Brg. Pier	115+15.19	20.83	570.08	570.08
L	115+25.19	20.83	570.07	570.08
M	115+35.19	20.83	570.05	570.09
N	115+45.19	20.83	570.02	570.10
O	115+55.19	20.83	569.99	570.11
P	115+65.19	20.83	569.96	570.11
Q	115+75.19	20.83	569.92	570.09
R	115+85.19	20.83	569.87	570.05
S	115+95.19	20.83	569.81	569.99
T	116+05.19	20.83	569.75	569.91
U	116+15.19	20.83	569.69	569.81
V	116+25.19	20.83	569.62	569.68
CL Brg. N. Abut.	116+36.69	20.83	569.53	569.53
Bk. N. Abut.	116+40.85	20.83	569.49	569.49

t:\2608-bris\struct\dgn\0320058-66408-007-EL04.dgn

DESIGNED - CMM
CHECKED - BJN
DRAWN - GJS
CHECKED - BJN

E-S

10-1-08

TOP OF SLAB ELEVATIONS IV
STRUCTURE NO. 032-0115

LOCHNER

H.W. LOCHNER, INC.
CONSULTING ENGINEERS & PLANNERS
20 NORTH WACKER DRIVE SUITE 1200
CHICAGO, IL 60606

SHEET NO. 7 OF 31 SHEETS	RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	*	(32, 47-4) HBK-4 & (G)N	GRUNDY	351	289
			CONTRACT NO. 66408		
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					
* FAI 80 & FAS 297 / FAU 392					