

VARIOUS ROUTES

100% STATE

* F.A.P. 72, F.A.P. 67, F.A.P. 75 & F.A.P. 668
 ** D-6 SPFLD-CLRLAKE DIRKSEN 2002

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	363	4
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 72088				

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	CONSTRUCTION TYPE CODE																
				ROADWAY				TRAFFIC SIGNALS		LIGHTING		SIDEWALK								
				FAP 67	FAP 75	FAP 668	FAI 72	CLRLAKE DIRKSEN	CLRLAKE HILL	FAP 67	FAP 75	FAP 67	FAP 668							
				1000-2A				Y03I-IF		Y030-IE		SFTY-IB								
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	335	335																
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	65	65																
20200100	EARTH EXCAVATION	CU YD	13545	12065	777	703														
20800150	TRENCH BACKFILL	CU YD	2077	1841		236														
25000210	SEEDING, CLASS 2A	ACRE	3.0	3.0																
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	465	435	15	15														
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	465	435	15	15														
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	465	435	15	15														
25100120	MULCH, METHOD 2	TON	18.5	17.5	0.5	0.5														
25200110	SODDING, SALT TOLERANT	SQ YD	14412	12381	948	1083														
25300500	TOP SOIL FOR PLANTING	CU YD	495	495																
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	625	575	25	25														
28000305	TEMPORARY DITCH CHECKS	FOOT	420.5	420.5																
28000400	PERIMETER EROSION BARRIER	FOOT	3313	3313																
28000500	INLET AND PIPE PROTECTION	EACH	189	156	3	30														
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	11832	11832																
31001500	LIME	TON	177	177																
31100700	SUB-BASE GRANULAR MATERIAL, TYPE A 8"	SQ YD	18260	13096	2425	2739														
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	1473	500	595	378														
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	1012	507	271	234														
35300615	PORTLAND CEMENT CONCRETE BASE COURSE 11 3/4"	SQ YD	443	443																
35501331	HOT-MIX ASPHALT BASE COURSE, 11 3/4"	SQ YD	7720	4443	1232	1545														
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	200	200																
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	45	23	5	5	12													
40600300	AGGREGATE (PRIME COAT)	TON	218	114	23	23	58													
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	2174	1319	448	407														
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1405	700	283	230	192													
40600990	TEMPORARY RAMP	SQ YD	354	155	45	38	116													
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	2705	1009			1696													
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	31	31																
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	5184	2749	672	631	1132													
40701881	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	SQ YD	14519	14519																
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	407	358	13	36														
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1286	833	239	214														
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	35462								27860	7602								
42400800	DETECTABLE WARNINGS	SQ FT	488	463		25														

* DENOTES SPECIALTY ITEM

SHEET 1 OF 7

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 DRAWN BY MLO
 CHECKED BY SJK
 DATE 08/05