

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	100% STATE																
				CONSTRUCTION TYPE CODE																
				ROADWAY				TRAFFIC SIGNALS		LIGHTING		SIDEWALK								
				FAP 67	FAP 75	FAP 668	FAI 72	CLRLAKE DIRKSEN	CLRLAKE HILL	FAP 67	FAP 75	FAP 67	FAP 668							
44000100	PAVEMENT REMOVAL	SQ YD	4218	3365	296	557														
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	31659	12327			19332													
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	32719	18604	7384	6731														
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	3749	2454	335	960														
44000300	CURB REMOVAL	FOOT	414	414																
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	15423	9379	3499	2545														
44000600	SIDEWALK REMOVAL	SO FT	68																	68
44002805	ISLAND REMOVAL	SQ FT	1330	1330																
44003100	MEDIAN REMOVAL	SO FT	28864	17188	7399	4277														
44004000	PAVED DITCH REMOVAL	FOOT	123	123																
44004250	PAVED SHOULDER REMOVAL	SQ YD	322	322																
44201847	CLASS D PATCHES, TYPE I, 17 INCH	SQ YD	4	4																
44201851	CLASS D PATCHES, TYPE II, 17 INCH	SQ YD	23	23																
44201855	CLASS D PATCHES, TYPE III, 17 INCH	SQ YD	18	18																
48101200	AGGREGATE SHOULDERS, TYPE B	TON	295	118		177														
48203006	HOT-MIX ASPHALT SHOULDERS, 2 1/4"	SQ YD	267	267																
48203012	HOT-MIX ASPHALT SHOULDERS, 3 3/4"	SQ YD	9397	3694		5703														
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	103	103																
50104400	CONCRETE HEADWALL REMOVAL	EACH	6	6																
50105220	PIPE CULVERT REMOVAL	FOOT	313	313																
* 51604000	DRILLED SHAFT IN ROCK	CU YD	4	2	2															
50901760	PIPE HANDRAIL	FOOT	294	154		140														
* 51604000	DRILLED SHAFT IN ROCK	CU YD	4	2	2															
54213447	END SECTIONS 12"	EACH	4	4																
54213459	END SECTIONS 24"	EACH	4	4																
54216185	REINFORCED CONCRETE PIPE TEE, 15" PIPE WITH 12" RISER	EACH	1	1																
54248510	CONCRETE COLLAR	CU YD	1.6	1.0		0.6														
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	2445	2337		108														
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	272	272																
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	238	238																
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	116	116																
550A0190	STORM SEWERS, CLASS A, TYPE 1 48"	FOOT	47	47																
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	458	458																
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	389	389																
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	459	459																
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	194			194														

F.A.I. 72, F.A.P. 67, F.A.P. 75 & F.A.P. 668
 ** D-6 SPFLD-CLRLAKE DIRKSEN 2002

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	363	5
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 72088				

* DENOTES SPECIALTY ITEM

SHEET 2 OF 7

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES DRAWN BY MLO CHECKED BY SJK DATE 08/05