

F.A.P. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	SANGAMON	363	29
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	
			CONTRACT NO. 72088

**TRENCHLESS PIPE, INSTALLATION, 18"**

STATION	OFFSET	FOOT
CLEAR LAKE AVE 29+60.00	RT	26
<b>TOTAL</b>		<b>26</b>

**TRENCHLESS PIPE, INSTALLATION, 24"**

STATION	OFFSET	FOOT
CLEAR LAKE AVE 31+50.00	RT	43
<b>TOTAL</b>		<b>43</b>

**TRENCHLESS PIPE, INSTALLATION, 48"**

STATION	OFFSET	FOOT
CLEAR LAKE AVE 29+95.00	LT&RT	131
<b>TOTAL</b>		<b>131</b>

**CONCRETE COLLAR, SPECIAL**

STATION	OFFSET	CU YD
CLEAR LAKE AVE 30+15.00	109' RT	0.60
<b>TOTAL</b>		<b>0.60</b>

**BRICK WALL REMOVAL**

STATION TO	STATION	OFFSET	FOOT
NORTH FRONTAGE RD 1+40.00	1+40.00	RT	8
1+40.00	1+56.00	RT	16
<b>TOTAL</b>			<b>24</b>

**STORM SEWER (WATER MAIN REQUIREMENTS) 36"**

STATION TO	STATION	OFFSET	FOOT
CLEAR LAKE AVE 21+00.00	22+80.00	LT	180
22+80.00	23+35.00	LT	55
23+35.00	25+58.00	LT	223
25+58.00	26+75.00	LT	117
26+75.00	26+84.38	LT	17
<b>TOTAL</b>			<b>592</b>

**STORM SEWER (WATER MAIN REQUIREMENTS) 24"**

STATION	OFFSET	FOOT
CLEAR LAKE AVE 31+50.00	RT	17
SOUTH FRONTAGE RD 15+93.10	41.75' LT	103
<b>TOTAL</b>		<b>120</b>

**RETAINING WALL REMOVAL**

STATION TO	STATION	OFFSET	CU YD
RE-ALIGNED HILL ST 1+27.00	2+06.00	RT	26
<b>TOTAL</b>			<b>26</b>

**STORM SEWER TO BE FILLED**

STATION TO	STATION	OFFSET	CU YD
CLEAR LAKE AVE 130+87.50	131+03.51	LT	1
20+05.39	20+15.69	LT	5
20+15.69	20+47.40	LT	5
20+41.38	20+47.40	LT	1
20+47.40	20+95.00	LT	6
30+30.71	3'x3' box	-	47
	35+01.77	RT	6
<b>TOTAL</b>			<b>71</b>

**CONCRETE ISLAND (SPECIAL)**

STATION TO	STATION	OFFSET	SQ FT
ISLANDS CLEAR LAKE/DIRKSEN NW QUADRANT	-	-	350
NE QUADRANT	-	-	510
SE QUADRANT	-	-	1317
SW QUADRANT	-	-	278
ISLAND K-MART/WALGREENS	-	-	261
<b>TOTAL</b>			<b>2,716</b>

**PARKING LOT PAVEMENT REMOVAL**

STATION TO	STATION	OFFSET	SQ YD
CLEAR LAKE AVE 127+35.00	127+48.00	LT	22
127+75.00	128+65.00	LT	190
131+00.00	132+00.00	LT	362
20+54.94	21+16.01	RT	35
26+82.00	27+07.00	LT	63
RE-ALIGNED HILL 0+90.00	1+48.00	LT	148
0+90.00	2+70.00	RT	87
HARDEE'S ENTRANCE 0+88.00	1+30.00	RT	48
WENDY'S LOT 1+62.00	1+88.00	RT	35
K-MART/WALGREEN'S 101+00.00	102+07.00	-	1787
SOUTH FRONTAGE RD 11+00.00	13+50.00	-	1257
13+50.00	15+00.00	-	1048
15+00.00	16+53.00	-	281
DIRKSEN PKWY 166+36.00	167+94.00	LT	209
168+00.00	169+44.00	RT	224
169+80.00	170+40.00	RT	86
<b>TOTAL</b>			<b>5,882</b>

SEE SHEET 161 FOR PARKING LOT PAVEMENT REMOVAL AT ENTRANCES

**REMOVE INLET BOX**

STATION	OFFSET	EACH
CLEAR LAKE AVE 123+23.18	34.83' LT	1
<b>TOTAL</b>		<b>1</b>

**CORRUGATED MEDIAN REMOVAL**

STATION TO	STATION	OFFSET	SQ FT
CLEAR LAKE AVE 20+14.00	20+35.00	LT	88
22+58.00	23+30.00	RT	358
24+44.00	24+80.00	LT	409
24+85.00	25+70.00	RT	827
28+52.00	29+35.00	LT	612
29+60.00	30+53.00	RT	710
34+78.00	35+75.00	LT	596
<b>TOTAL</b>			<b>3,600</b>

**STORM SEWER (WATERMAIN REQUIREMENT) 18"**

STATION TO	STATION	OFFSET	FOOT
CLEAR LAKE AVE 29+52.18	29+60.00	RT	35
<b>TOTAL</b>			<b>35</b>

**STORM SEWER (WATERMAIN REQUIREMENT) 48"**

STATION TO	STATION	OFFSET	FOOT
CLEAR LAKE AVE 29+95.00	-	RT	15
<b>TOTAL</b>			<b>15</b>

SHEET 7 OF 7

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**

DRAWN BY MLD  
 CHECKED BY SJK

DATE 8/2004