

c:\pw...wor-k\pwido\LAUGHLIN\INRL\0402041638\StormSewerSchedule.dgn
DATE

STORM SEWER TABLE														
STATION TO STATION	OFFSET	STORM SEWERS CLASS A												TRENCH BACKFILL CU YD
		12"	18"	24"	36"	48"	12"	18"	24"	30"	36"	42"	48"	
		TY 1	TY 1	TY 1	TY 1	TY 1	TY 2	TY 2	TY 2	TY 2	TY 2	TY 2	TY 2	
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	
CLEAR LAKE AVE														
123+23.18	LT	7												2
125+25.00 - 125+25.00	LT	10												
130+67.50 - 130+71.36	LT							6						2
131+35.00 - 131+61.03	LT	35												5
20+05.38 - 21+00.00	LT				116									72
20+36.65 - 21+00.00	LT	74												11
21+00.00	LT						14							5
21+00.00 - 21+80.34	LT	80												23
25+13.00 - 25+58.00	LT	45												6
25+58.00	LT	10												1
26+58.10 - 26+84.38	LT												46	61
26+84.38 - 28+57.32	LT											190		245
27+85.00 - 28+57.32	LT	73												10
28+57.32 - 29+95.00	LT												135	
29+40.00 - 29+50.00	LT	10												1
29+50.00 - 29+95.00	LT	43												
29+95.00 - 30+30.71	LT				32									
30+30.71 - 31+71.84	LT			42										
31+67.57 - 31+70.00	LT	24												
33+80.00	LT	16												
21+50.00 - 22+00.00	CL	52												7
22+00.00 - 22+65.00	CL	67												9
22+65.00 - 23+00.00	CL	37												5
23+00.00 - 23+65.00	CL	66												11
23+65.00 - 24+12.36	CL	47												10
24+80.00 - 25+00.00	CL	23												3
25+00.00 - 25+88.00	CL	88												17
25+88.00 - 25+90.00	CL	9												2
25+93.51 - 25+94.00	CL	4												1
26+71.74 - 27+03.60	CL	40												5
28+04.00 - 28+45.09	CL	52												7
29+45.00 - 29+55.00	CL	10												1
29+55.00 - 29+60.00	CL	16												3
29+60.00 - 29+70.00	CL	10												1
31+50.00	CL			15										
32+00.00	CL	8												
33+50.00	CL	8												
34+50.00	CL	8												
131+82.83 - 132+00.66	RT	19												4
20+65.00 - 20+80.00	RT	47												6
21+33.88 - 21+35.00	RT	5												1
22+30.00 - 22+35.13	RT	10												2
23+50.00 - 25+36.00	RT	186												28
25+36.00 - 25+36.50	RT						7							2
25+36.00 - 26+05.39	RT	71												14
29+60.00 - 29+70.00	RT	10												1
29+60.00 - 29+52.18	RT		35											
29+95.00	RT					15								
31+50.00	RT			17										
FAP 67 SUB-TOTAL		1320	35	106	116	15	27	0	0	0	0	46	325	584
RE-ALIGNED HILL ST														
0+80.00 - 0+90.00	LT	10												1
0+90.00 - 1+10.06	LT	25												6
0+90.00 - 1+02.76	LT&RT	53												7
0+95.00 - 1+05.00	RT	10												1
1+02.76 - 1+05.00	RT	8												1
1+02.76 - 2+92.89	RT											190		160
2+92.89 - 4+10.00	RT											118		163
4+10.00	LT&RT							54						50
4+10.00	LT&RT							12						27
4+10.00 - 4+25.00	LT	15												4
4+10.00 - 7+50.00	RT									332				
7+50.00 - 8+25.00	RT	71												13
8+25.00	LR&RT	30												7
7+50.00 - 9+00.00	RT									136				
9+00.00 - 9+25.00	RT	25												9
9+00.00	LT&RT										58			83
9+00.00 - 9+75.00	LT										82			
9+25.00	LT&RT	30												7
9+75.00 - 10+50.00	LT										82			
10+35.00 - 10+50.00	RT	15												3
10+35.00 - 10+50.00	LT						15							4
10+50.00	LT	20												3
10+50.00	LT&RT	30												8
10+50.00 - 11+50.00	LT							110						
11+50.00 - 11+75.00	LT	33												5
11+75.00	LT&RT	30												7
FAP 67 SUB-TOTAL		405	0	0	0	0	15	0	176	0	690	308	0	569

* F.A.I. 72, F.A.P. 67, F.A.P. 75 & F.A.P. 668
** D-6 SPFLD-CLR LAKE DIRKSEN 2002

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	363	107
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 72088				

TRENCH BACKFILL

STATION TO	STATION	OFFSET	CU YD
21+00.00	22+80.00	LT	58
22+80.00	23+35.00	LT	23
23+35.00	25+58.00	LT	165
25+58.00	26+75.00	LT	124
26+75.00	26+84.38	LT	21
0+42.00	0+42.00	LT&RT	15
TOTAL			406

QUANTITIES GIVEN FOR PIPE CULVERTS
SEE SHEET 108 FOR STORM SEWER TRENCH BACKFILL TOTALS

* IF REQUIRED DUE TO FINAL VERTICAL CLEARANCE A QUANTITY FOR "STORM SEWER (WATERMAIN REQUIREMENT)" HAS BEEN INCLUDED FOR THIS STORM SEWER.

SHEET 4 OF 5

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		STORM SEWER SCHEDULE

DRAWN BY MLO
CHECKED BY CWG
DATE 08/05