

F.A.P. 72, F.A.P. 67, F.A.P. 75 & F.A.P. 668
 ** D-6 SPFLD-CLRLAKE DIRKSEN 2002

F.A.P. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	SANGAMON	363	108
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	
		CONTRACT NO. 72088	

STORM SEWER TABLE														
STATION TO STATION	OFFSET	STORM SEWERS CLASS A												TRENCH BACKFILL CU YD
		12"	18"	24"	36"	48"	12"	18"	24"	30"	36"	42"	48"	
		TY 1	TY 1	TY 1	TY 1	TY 1	TY 2	TY 2	TY 2	TY 2	TY 2	TY 2	TY 2	
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
RE-ALIGNED HILL ST (CONT'D)														
11+50.00 - 12+25.00	LT								75					
12+25.00 - 13+00.00	LT							66						
13+00.00	LT	20												4
13+00.00	LT&RT	30												7
13+00.00 - 14+00.00	LT							88						
14+00.00 - 15+00.00	LT							90						
15+00.00 - 16+00.00	LT							90						
16+00.00 - 17+00.00	LT							94						35
17+00.00	LT&RT							30						15
17+00.00 - 17+50.00	LT							50						19
17+50.00 - 17+84.00	LT	34												5
17+00.00 - 17+84.00	RT	84												20
FAP 67 SUB-TOTAL		168	0	0	0	0	174	334	75	0	0	0	0	105
NORTH FRONTAGE RD														
1+40.00 - 1+47.00	RT	10												1
1+47.00 - 1+94.00	RT	65												11
1+94.00 - 2+80.00	RT	86												
2+80.00 - 2+90.00	RT							12						3
2+90.00	LT&RT							48						14
2+80.00 - 2+90.00	LT							10						3
2+90.00 - 3+12.08	LT							28						18
3+79.62 - 6+00.00	LT								110					
6+00.00	LT	8												
6+00.00 - 6+50.00	LT							54						16
6+00.00 - 7+00.00	LT								98					
6+50.00	LT&RT							30						8
6+50.00 - 6+60.00	LT							10						3
6+50.00 - 6+60.00	RT	10												2
7+00.00 - 8+00.00	LT			95										
8+00.00	LT	18												3
8+00.00	LT&RT	30												7
8+00.00 - 8+50.00	LT		50											
FAP 67 SUB-TOTAL		227	50	95	0	0	192	0	208	0	0	0	0	89
SOUTH FRONTAGE RD														
10+48.19 - 12+00.00	LT	147												
11+57.46 - 12+05.08	RT						50							14
12+00.00	LT&RT	26												3
12+00.00	LT	44												
12+97.79 - 13+34.67	LT			37										
13+37.36 - 13+40.00	LT		17											
13+30.00 - 13+40.00	LT		10											1
13+40.00	LT&RT							26						9
13+30.00 - 13+40.00	RT		10											1
12+05.08 - 12+52.61	RT		50											14
12+52.61 - 13+08.58	RT		50											15
13+08.58 - 13+58.58	RT		50											17
13+40.00 - 13+58.58	RT							29						
13+41.34 - 13+61.98	LT					32								14
FAP 67 SUB-TOTAL		217	187	37	0	32	50	55	0	0	0	0	0	88
DIRKSEN PARKWAY														
164+79.50 - 164+73.70	LT	9												1
166+61.87 - 166+64.06	LT	12												2
167+83.59	LT	9												2
169+25.84 - 169+26.08	LT	5												
170+61.55 - 170+61.86	LT	5												
164+89.00 - 165+76.36	RT									88				63
165+76.36	RT	8												1
165+76.36 - 166+09.94	RT	35												6
165+76.36 - 166+70.46	RT								94					71
166+70.46	RT	6												1
166+70.46 - 167+70.00	RT								100					86
167+70.00	RT	15												2
168+95.00 - 168+98.97	RT	4												1
FAP 668 SUB-TOTAL		108	0	0	0	0	0	0	0	194	88	0	0	236
FAP 67 TOTAL		2337	272	238	116	47	458	389	459	0	690	354	325	1435
FAP 668 TOTAL		108	0	0	0	0	0	0	0	194	88	0	0	236
GRAND TOTAL		2445	272	238	116	47	458	389	459	194	778	354	325	1671

SEE SHEET 107
 FOR TRENCH BACKFILL
 TOTALS AT PIPE CULVERTS

SHEET 5 OF 5

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

STORM SEWER SCHEDULE

DATE 08/05

DRAWN BY MLO
 CHECKED BY CWG

c:\pwworking\WIDOT\LAUGH\INRL\01834468\StormSewerSchedule.dgn
 DATE