* F.A.I. 72, F.A.P. 67, F.A.P. 75 & F.A.P. 668
** D-6 SPFLD-CLRLAKE DIRKSEN 2002

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	363	146
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 72088

LOCATION	THERMOPLASTIC PAVEMENT MARKING									PREFORMED PAVEMENT MARKING, TYPE B							URETHANE PAVEMENT MARKING				PAINT PAVEMENT MARKING	RAISED REFLECTIVE PAVEMENT MARKERS			PRISMATIC CURB REFLECTORS	
	YELLOW 5"	WHITE 5"	DOUBLE YELLOW 5"	WHITE 6"	SKIP-DASH WHITE 6"	SKIP-DASH YELLOW 6"	WHITE 8"	YELLOW 12"	WHITE 12"	SKIP-DASH WHITE 5"	WHITE 6"	SKIP-DASH WHITE 6"	WHITE 8"	WHITE 12"	WHITE 24"	LETTERS & SYMBOLS	YELLOW 5"	WHITE 5"	SKIP-DASH WHITE 5"	SKIP-DASH WHITE 6"	YELLOW 5"	ONE WAY CRYSTAL	ONE WAY AMBER	TWO WAY AMBER	ONE WAY CRYSTAL	ONE WAY AMBER
STATION TO STATION	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	SQ FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	EACH	EACH	EACH	EACH	EACH
FAP 75 DIRKSEN PKWY (CON'T)																										
RT 162+50 TO RT 162+85																					135					
LT 154+00 TO LT 163+00										230																
RT 154+00 TO RT 163+00										230																
LT 162+98 TO LT 163+09	24																									
LT 156+84 TO LT 157+89				105																						
LT 157+89 TO LT 158+88												26														
RT 156+93 TO RT 158+83												48														
RT 157+20 TO RT 160+17												74														
RT 158+83 TO RT 163+25				884																						
RT 160+17 TO RT 162+21				204																						
RT 160+17 TO RT 162+88				278																						
RT 163+25 TO LT 164+10												32														
RT 163+46 TO RT 164+50												36														
LT 162+97 TO LT 163+09								8																		
RT 162+21 TO RT 163+32									44																	
LT 157+01																8.8										
LT 157+88																8.8										
RT 158+89																17.6										
RT 159+67																17.6										
RT 160+20																17.6										
RT 160+49																17.6										
RT 161+30																35.2										
RT 162+15																35.2										
RT 162+70																8.8										
RT 162+80																8.8										
RT 162+90																17.6										
RT 162+76															38											
LT 163+09 TO RT 163+09															12											
RT 163+25															36											
LT 154+00 TO LT 162+40																						11				
RT 154+00 TO LT 156+33																							2			12
RT 154+00 TO RT 163+25																						12				
RT 157+00 TO LT 163+09																								1		32
RT 158+83 TO RT 163+25																						24				
RT 160+17 TO RT 163+32																						25				
FAP 668 DIRKSEN PKWY																										
RT 164+79 TO LT 170+32	557																									
RT 164+79 TO RT 170+32	553																									
RT 164+56 TO RT 164+79	49																									
LT 164+63 TO LT 173+57										230																
RT 164+63 TO RT 173+57										230																
RT 169+96 TO LT 172+22			846																							
LT 173+17 TO LT 173+57	40																									
RT 173+17 TO RT 173+57	40																									
LT 173+06 TO RT 173+71	151																									
LT 164+37 TO RT 164+37											87															
LT 164+45 TO RT 164+45											87															
RT 164+41 TO RT 164+61											27															
RT 164+46 TO RT 164+67											27															
LT 164+42 TO LT 164+59											26															
LT 164+48 TO LT 164+65											26															
LT 164+82 TO LT 167+17				235																						
LT 164+50 TO LT 168+04				354																						
℄ 164+50 TO ℄ 168+04				354																						
LT 167+17 TO LT 169+18												50														
LT 168+04 TO LT 169+96												48														
RT 169+70 TO RT 171+02												34														
RT 171+02 TO RT 172+22				120																						
LT 164+26 TO LT 164+82									41																	
RT 164+56 TO RT 164+80								19																		
℄ 169+96 TO ℄ 172+22								174																		
℄ 173+06 TO ℄ 173+71								66																		
LT 164+76 TO RT 164+76																17.6										
LT 164+80																8.8										
LT 165+58 TO RT 165+58																17.6										
FAP 75 SUB TOTALS	24	0	0	1471	0	0	0	8	44	460	0	216	0	0	86	193.6	0	0	0	0	135	72	2	1	0	44
FAP 668 SUB TOTALS	1390	0	846	1063	0	0	0	259	41	460	280	132	0	0	0	44.0	0	0	0	0	0	0	0	0	0	0

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKING SCHEDULE

DRAWN BY MLO
DATE 08/05 CHECKED BY SJK

SHEET 5 OF 19

c:\pw_work\PWIDOT\BLAUGHLINRL\d0183446\Pavement Marking Sched.dgn
•DATE•

BLANK, WESSELINK, COOK & ASSOCIATES ENGINEERS - CONSULTANTS DECATUR, ILLINOIS

SANGAMON COUNTY