

**SCHEDULE
PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID**

LOCATION	LINE 5"		LINE 6"		LINE 12"		LINE 24"		LETTERS AND SYMBOLS
	WHITE (FT)	YELLOW SKIP DASH & NO PASSING (FT)	WHITE (FT)	YELLOW SKIP DASH & NO PASSING (FT)	WHITE (FT)	YELLOW SKIP DASH & NO PASSING (FT)	WHITE (FT)	YELLOW SKIP DASH & NO PASSING (FT)	WHITE (SQ FT)
STA. 67+34.7 TO STA. 69+30.8 LT.	196								
STA. 67+62.20 TO STA. 69+54.4 LT.	193								
STA. 67+41 TO STA. 69+33.4 LT. (SKIP DASH)			48						
STA. 67+55 TO STA. 69+40.6 DBL. SOLID C				372					
STA. 67+75 TO STA. 69+54.4 RT. (DIAG.)					240				
COTTONWOOD DR. WEST							31		26
STA. 79+70							29		
STA. 80+72							25		
STA. 93+31							12		
WALNUT ST. EAST							12		
WALNUT ST. WEST							25		
STA. 94+26							14		
STA. 94+33							11		
STA. 66+50 LT. TURN ARROW									15.6
STA. 67+25 LT. TURN ARROW									15.6
STA. 69+20 LT. TURN ARROW									15.6
STA. 69+95 LT. TURN ARROW									15.6
STA. 78+20 LT. TURN ARROW									15.6
STA. 79+51 LT. TURN ARROW									15.6
STA. 80+94 LT. TURN ARROW									15.6
STA. 81+62 LT. TURN ARROW									15.6
STA. 82+87 LT. TURN ARROW									15.6
STA. 83+24 LT. TURN ARROW									15.6
STA. 84+26 LT. TURN ARROW									15.6
STA. 84+41 LT. TURN ARROW									15.6
STA. 85+60 LT. TURN ARROW									15.6
STA. 85+76 LT. TURN ARROW									15.6
STA. 87+54 LT. TURN ARROW									15.6
STA. 87+69 LT. TURN ARROW									15.6
STA. 89+12 LT. TURN ARROW									15.6
STA. 89+28 LT. TURN ARROW									15.6
STA. 91+02 LT. TURN ARROW									15.6
STA. 91+17 LT. TURN ARROW									15.6
STA. 92+56 LT. TURN ARROW									15.6
STA. 93+16 LT. TURN ARROW									15.6
STA. 94+54 LT. TURN ARROW									15.6
STA. 95+17 LT. TURN ARROW									15.6
STA. 110+31 LT., BIKE XING									23.4
SUB-TOTAL	389		48	372	240		184		
TOTAL	389		420	240	184		424		

THERMOPLASTIC PAVEMENT MARKING SCHEDULE

LOCATION	LENGTH (FT)	LINE - 5"		LINE - 6"		LINE - 12"
		WHITE (FT)	YELLOW (FT)	WHITE (FT)	YELLOW (FT)	WHITE (FT)
STA. 64+20 TO STA. 67+62.2	342	431		248	724	349
STA. 69+30.8 TO STA. 73+00	369	623	534	81	144	550
STA. 73+00 TO STA. 79+70	670	1268	1406			
STA. 80+73 TO STA. 93+46	1273	2531	2764	234		
STA. 94+15				104		
STA. 94+26 TO STA. 97+17	292	675	770			
STA. 97+17 TO STA. 97+91	73		20			
STA. 97+91 TO STA. 100+77	286	572	80			
STA. 100+77 TO STA. 101+57	80		20			
STA. 101+57 TO STA. 104+54	297	596	80			
STA. 104+54 TO STA. 105+35	81	81	20			
STA. 105+35 TO STA. 108+36	301	602	80			
STA. 108+36 TO STA. 109+27	91	91	30			
STA. 109+27 TO STA. 109+89	62	124	20			
STA. 109+89 TO STA. 110+68	79	79	20			
STA. 110+68 TO STA. 113+30	262	524	70			
STA. 113+30 TO STA. 114+16	86	86	20			
STA. 114+16 TO STA. 119+31	515	1030	130			
STA. 119+31 TO STA. 120+13	82	82	20			
STA. 120+13 TO STA. 121+00	87	174	20			
COTTONWOOD DR. WEST		33	66	116		
WALNUT ST. EAST		13	12	106		
WALNUT ST. WEST		8	2	108		
SUB-TOTAL		9623	6184	997	868	899
TOTAL		15807		1865		899

**SCHEDULE
SIDEWALK**

LOCATION	CURB CUT	SIDEWALK REMOVAL	PCC SIDEWALK, 4"	DETECTABLE WARNINGS
	FOOT	SQ FT	SQ FT	SQ FT
STA. 59+39.9 TO STA. 59+55.6 LT		91		
STA. 59+42 LT				10
STA. 59+39 TO STA. 63+57 LT			2119	
STA. 63+54 LT				10
STA. 63+55.4 LT	6			
STA. 63+81 LT	6			
STA. 63+84 LT				11
STA. 63+81 TO STA. 67+32.4 LT			1769	
STA. 69+21.6 TO STA. 70+42.5 LT			618	
STA. 70+41 LT				10
TOTAL	12	91	4506	41

**SCHEDULE
RELOCATE EXISTING SIGNS**

LOCATION	QUANTITY EACH
	STA. 66+16 33' RT. TO STA. 66+22 48' RT. (STOP SIGN)
STA. 65+78 36' RT. TO STA. 65+78 43' RT. (STREET SIGN)	1
STA. 70+39 54' LT. TO STA. 70+39 48' LT. (STREET SIGN)	1
TOTAL	3