SUMMARY OF QUANTITIES

	CODE NO.	SUMMARY OF QUANTITIES PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY FAP 662 80% FEDERAL 20% STATE	STRUCTURE S.N. 084-0521 80% FEDERAL 20% STATE	PPP RESURFACING 80% FED. 20% STATE FAP 662	SIDEWALK 80% STATE 20% VILLAGE
					CONSTRUCTION TYPE CODE			
					I000-2A		I000-2A	SFTY-1B
	60611600	COMBINATION CONCRETE CURB AND GUTTER, (SPECIAL)	FOOT	15	15			
*	63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	25	25			
*	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4			
*	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4			
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12			
	67100100	MOBILIZATION	L SUM	1	1			
	70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD	L SUM	1	1			
	70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21 701502	L SUM	1	1			
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD	L SUM	1	1			
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 701501	L SUM	1	1			
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1			
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12			
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10			
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1580	160		1420	
	70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	7365	7365			
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	20	20			
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3737	3172		565	
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	1350	1350			
	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	800	800			
*	78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	15807	1588		14219	
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1865	1197		668	
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	899	899			
*	78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SQ FT	424	63		361	
*	78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	389	389			
*	78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	420	420			
*	78004250	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 12"	FOOT	240	240			
*	78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	184	184			
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	190	38		152	
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4			
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	1049	1049			
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	188	188			
*	81012500	CONDUIT IN TRENCH, 1½" DIA., PVC	FOOT	329			329	

Rev.

*SPECIALTY ITEMS

USER NAME = laughlinrl	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 10.0000 ' / IN.	CHECKED -	REVISED -
PLOT DATE = Jun-28-2010 10:44:20AM	DATE -	REVISED -

Allen Henderson & Associates, Inc.
Civil and Structural Engineers Springfield, IL.
62703 Phone: (217)544-8033 IL. Design Firm
No. 184-001907

SUMMARY OF QUANTITIES

SCALE: NONE | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	H(RS-10,B-2)	SANGAMON	84	6
		CONTRACT NO. 72A73		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT