

SUMMARY OF QUANTITIES				ROADWAY FAP 662 80% FEDERAL 20% STATE	STRUCTURE S.N. 084-0521 80% FEDERAL 20% STATE	PPP RESURFACING <b>80% FED. 20% STATE FAP 662</b>	SIDEWALK 80% STATE 20% VILLAGE
CODE NO.	SUMMARY OF QUANTITIES PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
				1000-2A		1000-2A	SFTY-1B
* <del>81012500</del>	<del>CONDUIT IN TRENCH, 1 1/2" DIA., PVC</del>	<del>FOOT</del>	<del>329</del>			<del>329</del>	
* 81021540	CONDUIT, AUGERED, 1 1/2" DIA., PVC	FOOT	43			43	
* 81100500	CONDUIT, ATTACHED TO STRUCTURE, 1 1/2" DIA., GALVANIZED STEEL	FOOT	133			133	
* 81306500	REMOVE EXISTING JUNCTION BOX	EACH	1			1	
* 81400100	HANDHOLE	EACH	1			1	
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	329			329	
* 87100110	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 6 F	FOOT	2489			2489	
* 88600100	DETECTOR LOOP, TYPE I	FOOT	2058			2058	
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	2489			2489	
Z0001110	GAS VALVE TO BE ADJUSTED	EACH	1	1			
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
Z0024478	FLEXIBLE DELINEATORS	EACH	88	88			
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4	4			
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	4	4			
X6110089	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 12"	FOOT	60	60			
X6110097	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 42"	FOOT	124	124			
X0322494	CURB CUT	FOOT	12	12			
* X0326301	SETTING AND DRIVING PILES IN ROCK	EACH	28		28		
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1		
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1		1		
X5080600	MECHANICAL SPLICERS	EACH	60		60		
X6020088	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1	1			
X7240500	RELOCATE EXISTING SIGNS	EACH	3	3			
X7010502	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502 (SPECIAL)	L SUM	1	1			

\* SPECIALTY ITEMS