

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GIRDER 5				
LOCATION	STATION	OFFSET	THEORETICAL GRADE ELEVATION	ELEVATIONS ADJUSTED FOR DEAD LOAD DEFLECTION
CLP3	69520.00	9.88	511.95	511.95
CLP3U2	69521.08	9.88	511.96	511.96
A	69531.08	9.88	512.05	512.10
B	69541.08	9.88	512.15	512.25
C	69551.08	9.88	512.24	512.38
D	69561.08	9.88	512.34	512.51
E	69571.08	9.88	512.43	512.63
F	69581.08	9.88	512.53	512.73
G	69591.08	9.88	512.63	512.83
H	69601.08	9.88	512.72	512.91
J	69611.08	9.88	512.82	512.99
K	69621.08	9.88	512.91	513.05
L	69631.08	9.88	513.01	513.12
M	69641.08	9.88	513.11	513.18
N	69651.08	9.88	513.20	513.25
P	69661.08	9.88	513.30	513.31
Q	69671.08	9.88	513.39	513.40
CLP4	69676.50	9.88	513.44	513.44
R	69686.50	9.88	513.54	513.55
S	69696.50	9.88	513.64	513.67
T	69706.50	9.88	513.73	513.79
U	69716.50	9.88	513.83	513.92
V	69726.50	9.88	513.92	514.05
W	69736.50	9.88	514.02	514.18
X	69746.50	9.88	514.12	514.30
Y	69756.50	9.88	514.21	514.41
Z	69766.50	9.88	514.31	514.52
AA	69776.50	9.88	514.40	514.61
BB	69786.50	9.88	514.50	514.69
CC	69796.50	9.88	514.60	514.77
DD	69806.50	9.88	514.73	514.86
EE	69816.50	9.88	514.88	514.96
FF	69826.50	9.88	515.05	515.08
CLBRGW	69832.83	9.88	515.17	515.17
BKWABT	69836.00	9.88	515.23	515.23

GIRDER 6				
LOCATION	STATION	OFFSET	THEORETICAL GRADE ELEVATION	ELEVATIONS ADJUSTED FOR DEAD LOAD DEFLECTION
CLP3	69520.00	16.46	511.82	511.82
CLP3U2	69521.08	16.46	511.83	511.83
A	69531.08	16.46	511.93	511.98
B	69541.08	16.46	512.02	512.12
C	69551.08	16.46	512.12	512.26
D	69561.08	16.46	512.21	512.38
E	69571.08	16.46	512.31	512.50
F	69581.08	16.46	512.40	512.61
G	69591.08	16.46	512.50	512.70
H	69601.08	16.46	512.60	512.79
J	69611.08	16.46	512.69	512.86
K	69621.08	16.46	512.79	512.93
L	69631.08	16.46	512.88	512.99
M	69641.08	16.46	512.98	513.05
N	69651.08	16.46	513.08	513.12
P	69661.08	16.46	513.17	513.19
Q	69671.08	16.46	513.27	513.27
CLP4	69676.50	16.46	513.32	513.32
R	69686.50	16.46	513.41	513.43
S	69696.50	16.46	513.51	513.54
T	69706.50	16.46	513.61	513.66
U	69716.50	16.46	513.70	513.79
V	69726.50	16.46	513.80	513.92
W	69736.50	16.46	513.89	514.05
X	69746.50	16.46	513.99	514.17
Y	69756.50	16.46	514.09	514.29
Z	69766.50	16.46	514.18	514.39
AA	69776.50	16.46	514.28	514.48
BB	69786.50	16.46	514.37	514.57
CC	69796.50	16.46	514.48	514.64
DD	69806.50	16.46	514.60	514.73
EE	69816.50	16.46	514.75	514.84
FF	69826.50	16.46	514.92	514.96
CLBRGW	69832.83	16.46	515.04	515.04
BKWABT	69836.00	16.46	515.11	515.11

DESIGNED -	J.M.B.
CHECKED -	T.E.S.
DRAWN -	R KING
CHECKED -	J.M.B.

HOMER L. CHASTAIN & ASSOCIATES, LLP
CONSULTING ENGINEERS
DECATUR (217) 422-8544
CHICAGO (773) 714-0050
ROCKFORD (815) 489-0050
184-001397

**DECK ELEVATIONS - UNIT 2
STRUCTURE NUMBER 059-0510**

SHEET NO. 13 OF 51 SHEETS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	761	107B-2	MACOUPIN	98	43
FAP ROUTE 761 (IL RT 108)			CONTRACT NO. 72A94		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT			