

IL RTE 108 ROADWAY 80% FEDERAL 20% STATE	SN 059-0510 BRIDGE 80% FEDERAL 20% STATE
---	---

PAY CODE	ITEM	UNITS	TOTAL QUANTITY	CONSTRUCTION CODE TYPES	
				I000	X071-2A
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	44	44	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3	3	
40600300	AGGREGATE (PRIME COAT)	TON	10	10	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	98	98	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	116	116	
40600990	TEMPORARY RAMP	SQ YD	65	65	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	205	205	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	48	48	
44000100	PAVEMENT REMOVAL	SQ YD	245	245	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	713	713	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	2,037	2,037	
44004250	PAVED SHOULDER REMOVAL	SQ YD	285	285	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	256	256	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	78	78	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1	
50105220	PIPE CULVERT REMOVAL	FOOT	102	102	
50200100	STRUCTURE EXCAVATION	CU YD	690		690
50300225	CONCRETE STRUCTURES	CU YD	389.7		389.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	814.7		814.7
50300260	BRIDGE DECK GROOVING	SQ YD	2,378		2,378

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
c:\pwork\VPWIDOT\LAUGHLINR\021299\672494-Sht-500.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
761	107B-2	MACOUPIN	98	4
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT	CONTRACT NO. 72A94	