

S U M M A R Y O F Q U A N T I T I E S

CODE NO.	ITEM	UNIT	URBAN
			100% STATE
			Y030-IE
			TOTAL QTY
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1
81021330	CONDUIT PUSHED, 2" DIA., PVC	FOOT	351
81603000	UNIT DUCT, 600V, 2-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	1,819
81603010	UNIT DUCT, 600V, 2-1C NO.10, 1/C NO.10 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	1,163
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2,406
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	23
82106700	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT (MATERIAL ONLY)	EACH	3
82500340	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 480VOLT, 60 AMP	EACH	1
83053150	LIGHT POLE, ALUMINUM, 50 FT. M.H., 15 FT. DAVIT ARM - TWIN	EACH	11
67100100	MOBILIZATION	L SUM	1
X8303150	LIGHT POLE, ALUMINUM, 50 FT. M.H., 15 FT. DAVIT ARM, TWIN (MATERIAL ONLY)	EACH	1
83004601	LIGHT POLE, ALUMINUM, 50 FT. M.H., 15 FT. DAVIT ARM (MATERIAL ONLY)	EACH	2

QUANTITIES
STEVENSON DR/I 55 BUS
SECTION (15,110X)L
SANGAMON COUNTY

Rev.