

SUMMARY OF QUANTITIES

CODED NO.	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE (25-3) I-6					(25-3HB-2) B 90% FED. 10% STATE BRIDGE X271-2A
				90% FED. 10% STATE	90% FEDERAL 8% STATE 2% CITY	100% CITY	TRAFFIC SIGNALS PREEMPTORS Y031-3D		
				ROADWAY J000-2A	BIKE PATH & SIDEWALK J000-2A				
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2	2					
54010502	PRECAST CONCRETE BOX CULVERTS 5' X 2'	FOOT	170	170					
542A0241	PIPE CULVERTS, CLASS A, TYPE 1 36"	FOOT	62	62					
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	77	77					
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	24		24				
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1					
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1					
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2					
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1	1					
54215436	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 36"	EACH	2	2					
54215550	METAL END SECTIONS 15"	EACH	38	35	3				
54215973	REINFORCED CONCRETE PIPE ELBOW 18"	EACH	1	1					
54248510	CONCRETE COLLAR	CU YD	1.8	1.8					
54390310	INSERTION CULVERT LINER 60"	FOOT	137	137					
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	390	390					
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	6	6					
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	59	59					
550A0180	STORM SEWERS, CLASS A, TYPE 1 42"	FOOT	134	134					
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	98	98					
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	10	10					
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	327	327					
58700300	CONCRETE SEALER	SQ FT	2573					2573	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	180					180	
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	16	16					
60100955	PIPE DRAINS 15"	FOOT	777	708	69				
60107600	PIPE UNDERDRAINS 4"	FOOT	5796	5796					
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	254	254					
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	202					202	
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4					
60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1					
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3					
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1					
60224005	MANHOLES, TYPE A, 6'-DIAMETER, TYPE B GRATE	EACH	1	1					
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	20	20					
60236200	INLETS, TYPE A, TYPE B GRATE	EACH	1	1					
60237000	INLETS, TYPE A, TYPE 15 FRAME AND LID	EACH	2	2					
60237420	INLETS, TYPE A, TYPE 20 FRAME AND GRATE	EACH	3	3					
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	1	1					
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1					
60260100	INLETS TO BE ADJUSTED	EACH	4	4					
60260400	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1					
60500040	REMOVING MANHOLES	EACH	1	1					
60500060	REMOVING INLETS	EACH	8	8					
60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	437	437					
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	36	36					

CODED NO.	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE (25-3) I-6					(25-3HB-2) B 90% FED. 10% STATE BRIDGE X271-2A
				90% FED. 10% STATE	90% FEDERAL 8% STATE 2% CITY	100% CITY	TRAFFIC SIGNALS PREEMPTORS Y031-3D		
				ROADWAY J000-2A	BIKE PATH & SIDEWALK J000-2A				
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	10921	10921					
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	25681	25681					
60619300	CONCRETE MEDIAN, TYPE SB-6.06 (DOWELLED)	SQ FT	230	230					
60624600	CORRUGATED MEDIAN	SQ FT	2401	2401					
60900515	CONCRETE THRUST BLOCKS	EACH	8	8					
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	275	275					
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1					
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	3	3					
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2					
63200310	GUARDRAIL REMOVAL	FOOT	537	537					
63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	292	292					
63500105	DELINEATORS	EACH	40	40					
64200105	SHOULDER RUMBLE STRIPS	FOOT	5573	5573					
66400305	CHAIN LINK FENCE, 6'	FOOT	1239	1239					
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	16	16					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24	24					
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	24	24					
67100100	MOBILIZATION	L SUM	1	1					
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1					
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1					
70103800	TRAFFIC CONTROL, SPECIAL	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	650	650					
70103820	TRAFFIC CONTROL TEMPORARY FREEWAY ENDING	EACH	14	14					
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	96	96					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	790	790					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	18437	18437					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4197	4197					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	605	605					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2848	2848					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	370	370					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	13023	13023					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1075	1075					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	750	750					
* 72000100	SIGN PANEL - TYPE 1	SQ FT	514	514					
* 72000200	SIGN PANEL - TYPE 2	SQ FT	136	136					
* 72000300	SIGN PANEL - TYPE 3	SQ FT	2114	2114					
* 72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	1296	1296					
* 72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	24248	24248					
* 72700200	TUBULAR STEEL SIGN SUPPORT - BREAKAWAY	POUND	926	926					
* 73000100	WOOD SIGN SUPPORT	FOOT	71	71					
* 73400100	CONCRETE FOUNDATIONS	CU YD	49.4	49.4					
* 73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1	1					
* 73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	20	20					

* SPECIALTY ITEMS

Rev.

FILE NAME =	USER NAME = paul	DESIGNED - JWS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES, FAYETTE AVENUE	F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
SN\Projects\403-00072-61-70\dgn\Fayette\summary.dgn		DRAWN - PDB	REVISED -			57/70	(25-3)I-6 & (25-3HB-2)B	EFFINGHAM	839	5	
PLOT SCALE = 1/8" = 1' / IN.		CHECKED - BRM	REVISED -			CONTRACT NO. 74293					
PLOT DATE = 6/28/2010		DATE - 11-05-07	REVISED -			SCALE:	SHEET NO. 2 OF 4 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT