

SUMMARY OF QUANTITIES

CODED NO.	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE				
				(25-3) I-6				(25-3HB-2) B
				90% FED. 10% STATE ROADWAY J000-2A	90% FEDERAL 8% STATE 2% CITY BIKE PATH & SIDEWALK J000-2A	100% CITY TRAFFIC SIGNALS PREEMPTORS Y031-3D		90% FED. 10% STATE BRIDGE X271-2A
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	20	20				
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	1	1				
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	304	304				
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	11	11				
78200300	PRISMATIC CURB REFLECTOR	EACH	184	184				
78200410	GUARDRAIL MARKERS, TYPE A	EACH	12	12				
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2				
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1				
80500105	SERVICE INSTALLATION, TYPE A (MODIFIED)	EACH	3	3				
81012200	CONDUIT IN TRENCH, 3/4" DIA., PVC	FOOT	77	77				
81012400	CONDUIT IN TRENCH, 1 1/4" DIA., PVC	FOOT	255	255				
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	2993	2993				
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	721	721				
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	126	126				
81021550	CONDUIT, AUGERED 2" DIA., PVC	FOOT	373	373				
81021570	CONDUIT, AUGERED 3" DIA., PVC	FOOT	136	136				
81021590	CONDUIT, AUGERED 4" DIA., PVC	FOOT	987	987				
81100500	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., GALVANIZED STEEL	FOOT	311	311				
81100605	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC COATED GALVANIZED STEEL	FOOT	30	30				
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	270	270				
81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	3	3				
81300800	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18" X 12" X 6"	EACH	1	1				
81400100	HANDHOLE	EACH	20	20				
81400300	DOUBLE HANDHOLE	EACH	3	3				
81500100	GULFBOX JUNCTION	EACH	11	11				
81603000	UNIT DUCT, 600V, 2-1C NO. 8, 1/C NO. 8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	2514	2514				
81603030	UNIT DUCT, 600V, 2-1C NO. 4, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	5441	5441				
81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	5209	5209				
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	289	289				
81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	578	578				
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	10646	10646				
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	26	26				
82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	9	9				
82500380	LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 200AMP	EACH	1	1				
83004600	LIGHT POLE, ALUMINUM, 50 FT. M.H., 15 FT. DAVIT ARM	EACH	26	26				
83600357	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 8"	EACH	25	25				
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	100	100				
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	22	22				
84200804	REMOVE POLE FOUNDATION	EACH	22	22				
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1	1				

CODED NO.	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE				
				(25-3) I-6				(25-3HB-2) B
				90% FED. 10% STATE ROADWAY J000-2A	90% FEDERAL 8% STATE 2% CITY BIKE PATH & SIDEWALK J000-2A	100% CITY TRAFFIC SIGNALS PREEMPTORS Y031-3D		90% FED. 10% STATE BRIDGE X271-2A
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1	1				
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1	1				
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	2	2				
85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1	1				
86000100	MASTER CONTROLLER	EACH	1	1				
86200300	UNINTERRUPTIBLE POWER SUPPLY, EXTENDED	EACH	3	3				
86400100	TRANSCEIVER - FIBER OPTIC	EACH	4	4				
87100110	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 6F	FOOT	3438	3438				
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1626	1626				
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	6964	6964				
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2306	2306				
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	7406	7406				
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	90	90				
87502660	TRAFFIC SIGNAL POST, ALUMINUM 12 FT.	EACH	3	3				
87502680	TRAFFIC SIGNAL POST, ALUMINUM 14 FT.	EACH	8	8				
87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.	EACH	4	4				
87502720	TRAFFIC SIGNAL POST, ALUMINUM 18 FT.	EACH	2	2				
87602000	PEDESTRIAN PUSH-BUTTON POST	EACH	1	1				
87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	1	1				
87702850	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 24 FT.	EACH	1	1				
87702870	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 28 FT.	EACH	1	1				
87702890	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 32 FT.	EACH	1	1				
87702900	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 34 FT.	EACH	1	1				
87702910	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 36 FT.	EACH	1	1				
87702930	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 40 FT.	EACH	2	2				
87702950	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT.	EACH	1	1				
87702985	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 52 FT.	EACH	1	1				
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	51	51				
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	10.5	10.5				
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	63.5	63.5				
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	72.5	72.5				
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	10	10				
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	20	20				
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2	2				
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	2	2				
88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	4	4				
88040290	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2	2				
88102825	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	EACH	6	6				
88102845	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	EACH	1	1				

* SPECIALTY ITEMS