EROSION CONTROL SCHEDULE

LOCATION		EROSION CONTROL BLANKET	EARTH EXCAVATION FOR EROSION CONTROL	AGGREGATE (EROSION CONTROL)	PERIMETER EROSION BARRIER
STATION TO STATION	SIDE	(SQ YD)	(CU YD)	(TON)	(FOOT)
FAYETTE AVE					
42+03 TO 42+72	LT				70
42+72 TO 42+99	LT				31
42+50 TO 43+70	RT				129
46+38 TO 48+50	RT				211
46+75 TO 48+61	RT				187
46+50 TO 48+76	LT				227
47+75 TO 49+16	LT				141
48+58 TO 49+15	RT	300			
48+76 TO 49+35	LT	336			
50+67 TO 51+32	RT	399			
50+84 TO 51+32	RT				53
50+87 TO 51+51	LT	249			
51+32 TO 52+50	RT				120
52+50 TO 52+95	RT				53
51+51 TO 53+00	LT				149
51+38 TO 51+48	LT				16
51+48 TO 53+43	LT				195
58+25 TO 59+00	RT				79
59+00 TO 61+00	RT				203
61+00 TO 62+50	RT				150
FAYETTE RAMP A					
10+42	RT		2.96	1.13	
12+40 TO 15+46	RT				302
15+46 TO 17+71	RT				277
17+71 TO 19+76	RT				374
19+76 TO 21+92	RT				238
FAYETTE RAMP B					
10+55 TO 10+80	RT				57
10+80 TO 11+40	RT				94
11+13 TO 12+00	LT				88
11+40 TO 12+47	RT				146
12+00 TO 13+15	LT				116
12+47 TO 13+19	RT				84
12+58	RT		2.96	1.13	
13+63	RT		2.96	1.13	
FAYETTE RAMP C					
18+00 TO 20+01	RT				345
20+01 TO 20+81	RT				139
18+50 TO 19+00	LT				66
19+00 TO 20+00	LT				101
FAYETTE RAMP D					
10+82 TO 11+49	RT				97
11+49 TO 12+02	RT				68
12+02 TO 12+85	RT				106
I-57/70					
2139+39 TO 2144+97	LT				558
2139+50 TO 2145+30	RT				580
2147+42 TO 2154+50	LT				708
2147+78 TO 2152+63	RT				486
SUBTOTAL		1284	8.88	3.39	7044
TOTAL		1284	9	4	7044

INLET AND PIPE PROTECTION SCHEDULE

LOCATION			INLET AND PIPE PROTECTION
STATION	SIDE	OFFSET	(EACH)
FAYETTE AVE			
37+23	RT	39	1
38+00	LT	36	1
38+00	RT	19	1
38+22	RT	50	1
38+65	LT	44	1
38+66	RT	48	1
39+50	RT	54	1
39+50	RT	25	1
40+00	LT	37	1
40+00	LT	43	1
41+00	LT	54	1
42+00	LT	37	1
42+00	RT	38	1
42+00	RT	75	1
43+70	LT	37	1
44+00	RT	49	1
46+25	LT	37	1
46+50	RT	37	1
48+00	LT	37	1
48+00	RT	37	1
48+77	LT	99	1
50+78	LT	92	1
52+00	LT	37	1
52+00	RT	37	1
53+60	LT	37	1
53+60	RT	37	1
55+00	LT	49	1
55+00	RT	41	1
56+50	LT	49	1
57+50	LT	48	1
57+50	RT	37	1
59+00	LT	39	1
60+00	LT	36	1
60+00	RT	37	1
61+00	LT	34	1
61+25	RT	37	1
62+00	LT	33	1
62+50	RT	37	1
63+00	LT	31	1
63+75	LT	30	1
63+75	RT	37	1
65+00	LT	28	1
65+00	RT	38	1
66+25	LT	28	1
		SUBTOTAL	44

LOCATION			INLET AND PIPE PROTECTION
STATION	SIDE	OFFSET	(EACH)
66+25	RT	38	1
67+50	LT	28	1
67+50	RT	38	1
67+74	RT	51	1
67+80	LT	54	1
68+86	LT	48	1
68+98	RT	77	1
69+09	RT	47	1
69+17	LT	28	1
69+24	LT	45	1
69+55	RT	38	1
69+55	RT	50	1
69+84	RT	51	1
69+90	LT	40	1
70+07	LT	28	1
70+07	LT	39	1
70+41	RT	58	1
70+59	LT	43	1
70+79	LT	28	1
70+88	LT	44	1
71+48	RT	62	1
72+00	LT	28	1
72+00	RT	38	1
72+00	RT	67	1
72+10	LT	28	1
72+10	RT	38	1
72+20	LT	28	1
72+20	LT	38	1
73+02	RT	51	1
FAYETTE RAMP A			
11+86	LT	26	1
FAYETTE RAMP B			
16+50	LT	79	1
FAYETTE RAMP C			
12+15	RT	24	1
BIKE TRAIL			
11+50	LT	26	1
47+91	RT	18	1
S. FRONTAGE ROAD			
9+12	LT	48	1
ILLINI DRIVE			
0+71	LT	41	1
		SUBTOTAL	36
		TOTAL	80

DELINEATOR SCHEDULE

LOCATION		DELINEATORS
STATION	SIDE	(EACH)
FAYETTE RAMP A		
17+08 TO 20+02	LT/RT	6
FAYETTE RAMP C		
10+00 TO 17+86	LT/RT	19
FAYETTE RAMP D		
14+50 TO 20+00	LT/RT	10
I-57/70		
2133+37.48 TO 2136+08.06	LT	3
2135+39.29 TO 2136+70.10	RT	2
	TOTAL	40

TEMPORARY DITCH CHECKS SCHEDULE

LOCATION			TEMPORARY DITCH CHECKS
STATION	SIDE	OFFSET	(FOOT)
FAYETTE AVE			
39+00	RT	46	30
41+50	RT	69	41
56+18	LT	173	13
56+86	RT	200	13
57+55	LT	108	13
58+12	LT	73	17
58+23	RT	141	13
58+97	LT	70	23
60+47	LT	65	28
61+16	RT	77	18
61+98	LT	64	31
63+48	LT	63	34
64+17	RT	63	17
64+95	LT	62	38
67+16	RT	55	14
FAYETTE RAMP A			
11+60	RT	40	16
12+42	RT	49	16
13+09	RT	61	16
13+69	RT	69	16
14+51	RT	82	16
15+33	RT	109	16
16+15	RT	585	16
17+21	RT	185	16
17+88	RT	238	19
18+53	RT	280	25
19+17	RT	303	25
19+81	RT	304	25
20+82	RT	302	25
FAYETTE RAMP B			
11+15	RT	30	19
11+65	RT	28	23
11+80	RT	185	25
12+05	RT	167	25
12+10	RT	28	21
12+25	RT	162	25
12+45	RT	28	21
12+75	RT	28	23
13+04	RT	30	23
13+27	RT	40	23
FAYETTE RAMP C			
10+23	LT	29	10
10+85	RT	40	23
10+96	LT	34	17
11+34	LT	39	25
11+48	RT	42	23
11+71	LT	42	25
12+10	LT	46	25
12+48	LT	57	15
12+69	RT	37	23
13+27	RT	28	23
13+82	LT	42	23
15+15	LT	42	23
15+68	RT	28	23
16+38	LT	42	23
16+58	RT	27	18
17+50	RT	43	21
17+61	LT	42	23
FAYETTE RAMP D			
11+73	RT	141	25
14+18	RT	38	23
17+18	RT	35	17
BIKE TRAIL			
47+73	LT	16	18
I-57/70			
2137+71	LT	79	18
2138+20	LT	84	33
2138+72	LT	84	27
2140+17	LT	88	22
2141+59	RT	92	11
2141+61	LT	92	24
2143+06	LT	95	23
2143+18	RT	90	16
2144+52	LT	97	25
2144+68	RT	87	15
2147+50	LT	88	33
2147+82	RT	85	16
2149+00	LT	88	21
2149+32	RT	82	14
2150+50	LT	88	20
2150+81	RT	82	12
2152+31	RT	85	15
2152+75	LT	88	20
		TOTAL	1629

GUARDRAIL SCHEDULE

LOCATION		STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 2	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL, TYPE 1, (SPECIAL) TANGENT	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	GUARDRAIL REMOVAL	GUARDRAIL MARKERS, TYPE A	TERMINAL MARKER - DIRECT APPLIED
STATION	SIDE	(FOOT)	(EACH)	(EACH)	(EACH)	(FT)	(FOOT)	(EACH)	(EACH)
FAYETTE AVE.									
45+34.32 TO 48+58.28	RT						324		
46+34.38 TO 48+78.13	RT	150		1	1			4	1
46+61.28 TO 47+85.26	LT						126		
48+40.71 TO 48+96.96	LT		1	1				4	
51+22.26 TO 52+08.25	LT						87		
51+30.12 TO 53+48.87	LT	125		1	1			4	1
I-57/70									
2159+33.22 TO 2162+25.00	LT					292			
TOTAL		275	1	3	2	292	537	12	2

FILE NAME = S:\Projects\403-00072_57-70\dgn\Fayette\schedules.dgn	USER NAME = paul	DESIGNED - ESW	REVISED - 08-02-10	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES, FAYETTE AVENUE	F.A.I RTE. 57/70	SECTION (25-3)I-6	COUNTY EFFINGHAM	TOTAL SHEETS 839 / SHEET NO. 36
	PLOT SCALE = 50.0000 ' / IN.	DRAWN - ESW	REVISED -					CONTRACT NO. 74293	
	PLOT DATE = 8/3/2010	CHECKED - BRM	REVISED -						
		DATE - 11-16-07	REVISED -		SCALE: SHEET NO. 6 OF 6 SHEETS STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	