

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000	SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A			
				90% FED	90% FED	90% FED	90% FED	90% FED			
				10% STATE	10% STATE	10% STATE	10% STATE	10% STATE			
				ROADWAY	SN 060-0195 ALHAMBRA RD	SN 060-0198 NEW DOUGLAS	SN 060-0196 I-55 OVER RR	SN 060-0197 I-55 OVER RR			
20200100	EARTH EXCAVATION	CU YD	544	544							
20400800	FURNISHED EXCAVATION	CU YD	100	100							
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1632	1632							
25000210	SEEDING, CLASS 2A	ACRE	0.24	0.24							
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	21.6	21.6							
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	21.6	21.6							
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	21.6	21.6							
25100105	MULCH, METHOD 1	ACRE	0.24	0.24							
28000520	ABOVE GRADE INLET PROTECTION	EACH	7	7							
28100101	STONE RIPRAP, CLASS A1	SQ YD	26				13	13			
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	1632	1632							
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	128.5	128.5							
40600300	AGGREGATE (PRIME COAT)	TON	618	618							
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1525	1525							
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	854	854							
40600990	TEMPORARY RAMP	SQ YD	950	950							
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	19627	19627							
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	17683	17683							
42100360	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 13"	SQ YD	1451	1451							
42100615	PAVEMENT REINFORCEMENT	SQ YD	1451	1451							
42101300	PROTECTIVE COAT	SQ YD	1451	1451							
44000100	PAVEMENT REMOVAL	SQ YD	1451	1451							
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	147894	147894							
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	93516	93516							
44004356	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	1584			1584					
44004250	PAVED SHOULDER REMOVAL	SQ YD	2933	2933							
44200577	CLASS A PATCHES, TYPE II, 12 INCH	SQ YD	301	301							
44200581	CLASS A PATCHES, TYPE III, 12 INCH	SQ YD	84	84							
44200583	CLASS A PATCHES, TYPE IV, 12 INCH	SQ YD	84	84							
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SQ YD	461	461							
44213000	PATCHING REINFORCEMENT	SQ YD	916	916							

FILE NAME =	USER NAME = conoverpj	DESIGNED -	REVISED -
ct:\pw\work\pw\dot\conoverpj\d0128605\d8	6601-sht\plan.dgn	DRAWN -	REVISED -
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 6/23/2010	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 1 OF 4 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	60-3RS-1,60-(3HB,3HB-1)I	MADISON	123	3
CONTRACT NO. 76601				
ILLINOIS FED. AID PROJECT				