

UNDERDRAIN SCHEDULE												
STATION	SHOULDER REMOVAL & REPLACEMENT, 12.5"		PIPE UNDERDRAIN REMOVAL		PIPE UNDERDRAINS 4"		PIPE UNDERDRAINS (SPECIAL)		CONCRETE HEADWALLS FOR PIPE DRAINS		PAINT PAVEMENT MARKING LETTERS & SYMBOLS	
	FOOT		FOOT		FOOT		FOOT		EACH		SQ FT	
NORTHBOUND	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE
520+12.50 - 509+00	1112.5	1112.5	1200.5	1256.5	1112.5	1112.5	88	144	4	4	8	8
509+00 - 494+00	1500	1500	1566	1608	1500	1500	66	108	3	3	6	6
494+00 - 479+00	1500	1500	1566	1608	1500	1500	66	108	3	3	6	6
479+00 - 466+00	1500	1500	1566	1608	1500	1500	66	108	3	3	6	6
466+00 - 449+00	1500	1500	1588	1644	1500	1500	88	144	4	4	8	8
449+00 - 434+00	1500	1500	1566	1608	1500	1500	66	108	3	3	6	6
434+00 - 419+00	1500	1500	1588	1644	1500	1500	88	144	4	4	8	8
419+00 - 404+00	1500	1500	1566	1608	1500	1500	66	108	3	3	6	6
404+00 - 389+00	1500	1500	1566	1608	1500	1500	66	108	3	3	6	6
389+00 - 374+00	835	1500	1566	1608	1500	1500	66	108	3	3	6	6
374+00 - 359+00	1500	1500	1566	1608	1500	1500	66	108	3	3	6	6
359+00 - 344+00	628	1500	1566	1608	1500	1500	66	108	3	3	6	6
344+00 - 329+00	1260	1500	1566	1608	1500	1500	66	108	3	3	6	6
329+00 - 314+00	1322	1321	1388	1518	1322	1410	66	108	3	3	6	6
314+00 - 299+00	1500	1500	1588	1644	1500	1500	88	144	4	4	8	8
299+00 - 284+00	1500	1500	1566	1608	1500	1500	66	108	3	3	6	6
284+00 - 269+00	1500	1500	1566	1608	1500	1500	66	108	3	3	6	6
269+00 - 254+00	1500	1500	1566	1608	1500	1500	66	108	3	3	6	6
254+00 - 250+00	400	400	422	436	400	400	22	36	1	1	2	2
SOUTHBOUND												
520+12.50 - 509+00	1112.5	1112.5	1200.5	1256.5	1112.5	1112.5	88	144	4	4	8	8
509+00 - 494+00	1500	1500	1566	1608	1500	1500	66	108	3	3	6	6
494+00 - 479+00	1500	1500	1566	1608	1500	1500	66	108	3	3	6	6
479+00 - 466+00	1500	1500	1566	1608	1500	1500	66	108	3	3	6	6
466+00 - 449+00	1500	1500	1588	1644	1500	1500	88	144	4	4	8	8
449+00 - 434+00	1500	1500	1566	1608	1500	1500	66	108	3	3	6	6
434+00 - 419+00	1500	1500	1588	1644	1500	1500	88	144	4	4	8	8
419+00 - 404+00	658	785.5	1566	1608	1500	1500	66	108	3	3	6	6
404+00 - 389+00	1500	1500	1566	1608	1500	1500	66	108	3	3	6	6
389+00 - 374+00	376	1500	1566	1608	1500	1500	66	108	3	3	6	6
374+00 - 359+00	518	721	1566	1608	1500	1500	66	108	3	3	6	6
359+00 - 344+00	911	1500	1566	1608	1500	1500	66	108	3	3	6	6
344+00 - 324+00	1397	1500	1566	1608	1500	1500	66	108	3	3	6	6
329+00 - 314+00	1321	1321	1387	1429	1321	1321	66	108	3	3	6	6
314+00 - 299+00	1500	1500	1588	1644	1500	1500	88	144	4	4	8	8
299+00 - 284+00	1500	1500	1566	1608	1500	1500	66	108	3	3	6	6
284+00 - 269+00	1500	1500	1566	1608	1500	1500	66	108	3	3	6	6
269+00 - 254+00	1500	1500	1566	1608	1500	1500	66	108	3	3	6	6
254+00 - 250+00	400	400	422	436	400	400	22	36	1	1	2	2
SUB-TOTALS	48251	52173.5	56264	58004	53668	53756	2596	4248	118	118	236	236
TOTALS	100424.5		114268		107424		6844		236		472	

PAVEMENT REMOVAL AND REPLACEMENT SCHEDULE									
STATION	PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL	EARTH EXCAVATION	AGGREGATE BASE COURSE, TYPE A 12"	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	CRPCC PAVEMENT, 13"	PAVEMENT REINFORCEMENT, 13"	PROTECTIVE COAT	HMA SHOULDERS, 9"
	SQ YD	SQ YD	CU YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD
SB STA. 414+30 - 405+88		935.6							935.6
SB STA. 411+28 - 408+88	640.0		340.0	720.0	720.0	640.0	640.0	640.0	
SB STA. 413+65.5 - 406+51		476.3							476.3
SB STA. 368+07.5 - 359+06.5		1001.1							1001.1
SB STA. 365+09 - 362+05	810.7		304.0	912.0	912.0	810.7	810.7	810.7	
SB STA. 367+46.5 - 359+67.5		519.3							519.3
TOTALS	1450.7	2932.3	544.0	1632.0	1632.0	1450.7	1450.7	1450.7	2932.3

LOCATION	FURNISHED EXCAVATION
	CU YD
ESTIMATED QUANTITY FOR EMBANKMENT TO BRING EXISTING FOUNDATIONS INTO COMPLIANCE WITH THE BDE MANUAL, SECTION 50-3.04(C)	100
TOTALS	100

LOCATION	PAINT PAVEMENT MARKING	PRISMATIC CURB REFLECTOR
	FOOT	EACH
RAMP B	63.4	12
RAMP D	51.4	12
TOTALS	114.8	24