

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	90% FED./10% STATE			CODE NO	ITEM	UNIT	TOTAL QUANTITIES	90% FED./10% STATE		
				100% STATE	-----	-----					100% STATE	-----	-----
				1000	Y002-1C					1000	Y002-1C		
X4830030	PORTLAND CEMENT CONCRETE SHOULDERS 8" (SPECIAL)	SQ YD	13109	13109		40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	56418	56418			
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	24	24		40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	121	121			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	40	40		42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	128	128			
20200100	EARTH EXCAVATION	CU YD	2490	2490		42100380	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 14"	SQ YD	7978	7978			
20300100	CHANNEL EXCAVATION	CU YD	1000	1000		42100615	PAVEMENT REINFORCEMENT	SQ YD	7978	7978			
20400800	FURNISHED EXCAVATION	CU YD	18350	18350		42101300	PROTECTIVE COAT	SQ YD	7978	7978			
25000200	SEEDING, CLASS 2	ACRE	75	75		44000100	PAVEMENT REMOVAL	SQ YD	8106	8106			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	6750	6750		44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	320705	320705			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	6750	6750		44000300	CURB REMOVAL	FOOT	3861	3861			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	6750	6750		44004250	PAVED SHOULDER REMOVAL	SQ YD	75759	75759			
25100115	MULCH, METHOD 2	ACRE	75	75		44200934	CLASS B PATCHES, TYPE II, 8 INCH	SQ YD	249	249			
25100630	EROSION CONTROL BLANKET	SQ YD	1608	1608		44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQ YD	443	443			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	7500	7500		44200962	CLASS B PATCHES, TYPE III, 9 INCH	SQ YD	20	20			
28000305	TEMPORARY DITCH CHECKS	FOOT	3438	3438		44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	66	66			
28000400	PERIMETER EROSION BARRIER	FOOT	3200	3200		44213100	PAVEMENT FABRIC	SQ YD	20	20			
28000500	INLET AND PIPE PROTECTION	EACH	68	68		44213200	SAW CUTS	FOOT	4621	4621			
28100103	STONE RIPRAP, CLASS A2	SQ YD	25972	25972		48101200	AGGREGATE SHOULDERS, TYPE B	TON	18836	18836			
28200200	FILTER FABRIC	SQ YD	25972	25972		48203045	HOT-MIX ASPHALT SHOULDERS, 12"	SQ YD	5742	5742			
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	50790	50790		48203100	HOT-MIX ASPHALT SHOULDERS	TON	74836	74836			
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	2938	2938		50104400	CONCRETE HEADWALL REMOVAL	EACH	5	5			
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	20122	20122		50105220	PIPE CULVERT REMOVAL	FOOT	2298	2298			
35600724	HOT-MIX ASPHALT BASE COURSE WIDENING, 12"	SQ YD	50773	50773		50300225	CONCRETE STRUCTURES	CU YD	36	36			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	262	262		50800105	REINFORCEMENT BARS	POUND	250	250			
40600300	AGGREGATE (PRIME COAT)	TON	1381	1381		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3120	3120			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	5502	5502		50800515	BAR SPLICERS	EACH	192	192			
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	2589	2589		Z0026407	TEMPORARY SHEET PILING	SQ FT	694	694			
40600990	TEMPORARY RAMP	SQ YD	1126	1126		54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2	2			
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	117654	117654		54002020	EXPANSION BOLTS 3/4 INCH	EACH	208	208			
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	38629	38629		54010803	PRECAST CONCRETE BOX CULVERT 8' X 3'	FOOT	148	148			
						54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2			