

TEMPORARY PAVEMENT MARKING - LINE 6''	
LOCATION	FOOT
LT. STA. 668+00 TO LT. STA. 717+14 (WHITE EDGELINE)	4,914
RT. STA. 668+00 TO RT. STA. 723+75 (WHITE EDGELINE)	5,575
RT. STA. 668+00 TO RT. STA. 734+00 (YELLOW EDGELINE)	6,600
LT. STA. 668+00 TO LT. STA. 1263+98 (YELLOW EDGELINE)	59,598
LT. STA. 668+00 TO LT. STA. 1263+98 (WHITE SKIP-DASH)	14,900
RT. STA. 668+00 TO RT. STA. 1263+98 (WHITE SKIP-DASH)	14,900
LT. STA. 728+68 TO LT. STA. 734+00 (WHITE EDGELINE)	532
RT. STA. 730+44 TO RT. STA. 747+20 (WHITE EDGELINE)	1,676
LT. STA. 734+00 TO LT. STA. 743+00 (WHITE EDGELINE)	900
RT. STA. 734+00 TO RT. STA. 743+00 (YELLOW EDGELINE)	900
LT. STA. 743+00 TO LT. STA. 746+44 (WHITE EDGELINE)	344
RT. STA. 743+00 TO RT. STA. 1002+24 (YELLOW EDGELINE)	25,924
LT. STA. 753+42 TO LT. STA. 818+30 (WHITE EDGELINE)	6,488
RT. STA. 758+76 TO RT. STA. 790+07 (WHITE EDGELINE)	3,131
RT. STA. 797+15 TO RT. STA. 822+02 (WHITE EDGELINE)	2,487
LT. STA. 822+17 TO LT. STA. 848+88 (WHITE EDGELINE)	2,671
RT. STA. 836+49 TO RT. STA. 1102+26 (WHITE EDGELINE)	26,577
LT. STA. 856+00 TO LT. STA. 1001+45 (WHITE EDGELINE)	14,545
LT. STA. 1001+45 TO LT. STA. 1003+72 (WHITE EDGELINE)	227
RT. STA. 1002+24 TO RT. STA. 1004+51 (YELLOW EDGELINE)	227
LT. STA. 1003+72 TO LT. STA. 1096+16 (WHITE EDGELINE)	9,244
RT. STA. 1004+51 TO RT. STA. 1114+80 (YELLOW EDGELINE)	11,029
LT. STA. 1107+49 TO LT. STA. 1114+80 (WHITE EDGELINE)	731
RT. STA. 1109+01 TO RT. STA. 1127+00 (WHITE EDGELINE)	1,799
LT. STA. 1114+80 TO LT. STA. 1121+00 (WHITE EDGELINE)	620
RT. STA. 1114+80 TO RT. STA. 1121+00 (YELLOW EDGELINE)	620
LT. STA. 1121+00 TO LT. STA. 1126+60 (WHITE EDGELINE)	560
RT. STA. 1121+00 TO RT. STA. 1263+98 (YELLOW EDGELINE)	14,298
LT. STA. 1133+59 TO LT. STA. 1263+98 (WHITE EDGELINE)	13,039
RT. STA. 1138+51 TO RT. STA. 1263+98 (WHITE EDGELINE)	12,547
IL 140 RAMPS:	
STA. 108+09 TO STA. 120+10 (WHITE EDGELINE)	1,201
STA. 200+00 TO STA. 206+68 (WHITE EDGELINE)	668
STA. 307+43 TO STA. 319+46 (WHITE EDGELINE)	1,203
STA. 400+00 TO STA. 406+96 (WHITE EDGELINE)	696
NBL REST AREA RAMPS:	
STA. 100+00 TO STA. 107+12 (WHITE EDGELINE)	712
STA. 135+34 TO STA. 149+18 (WHITE EDGELINE)	1,384
SBL REST AREA RAMPS:	
STA. 100+00 TO STA. 107+08 (WHITE EDGELINE)	708
STA. 135+71 TO STA. 150+67 (WHITE EDGELINE)	1,496
IL 143 RAMPS:	
STA. 110+05 TO STA. 122+04 (WHITE EDGELINE)	1,199
STA. 200+00 TO STA. 206+99 (WHITE EDGELINE)	699
STA. 310+21 TO STA. 322+02 (WHITE EDGELINE)	1,181
STA. 400+00 TO STA. 406+75 (WHITE EDGELINE)	675
TOTAL =	269,425

TEMPORARY PAVEMENT MARKING - LINE 12''	
LOCATION	FOOT
IL 140 RAMPS:	
STA. 100+33 TO STA. 110+61 (OUTSIDE SHOULDER)	595
STA. 205+31 TO STA. 218+81 (OUTSIDE SHOULDER)	765
STA. 300+38 TO STA. 309+97 (OUTSIDE SHOULDER)	544
STA. 405+30 TO STA. 418+62 (OUTSIDE SHOULDER)	765
IL 143 RAMPS:	
STA. 100+34 TO STA. 112+54 (OUTSIDE SHOULDER)	697
STA. 205+29 TO STA. 219+46 (OUTSIDE SHOULDER)	816
STA. 300+34 TO STA. 312+51 (OUTSIDE SHOULDER)	697
STA. 405+24 TO STA. 418+32 (OUTSIDE SHOULDER)	748
TOTAL =	5,627

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	
LOCATION	SQ. FT.
PIPE UNDERDRAIN OUTLETS	695
TOTAL =	695

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12''	
LOCATION	FOOT
IL 140 RAMPS:	
STA. 100+33 TO STA. 110+61 (OUTSIDE SHOULDER)	595
STA. 205+31 TO STA. 218+81 (OUTSIDE SHOULDER)	765
STA. 300+38 TO STA. 309+97 (OUTSIDE SHOULDER)	544
STA. 405+30 TO STA. 418+62 (OUTSIDE SHOULDER)	765
IL 143 RAMPS:	
STA. 100+34 TO STA. 112+54 (OUTSIDE SHOULDER)	697
STA. 205+29 TO STA. 219+46 (OUTSIDE SHOULDER)	816
STA. 300+34 TO STA. 312+51 (OUTSIDE SHOULDER)	697
STA. 405+24 TO STA. 418+32 (OUTSIDE SHOULDER)	748
TOTAL =	5,627

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4''	
LOCATION	FOOT
IL 140 RAMPS:	
STA. 100+33 TO STA. 108+09 (WHITE EDGELINE)	776
STA. 100+33 TO STA. 108+09 (YELLOW EDGELINE)	776
STA. 206+68 TO STA. 218+81 (WHITE EDGELINE)	1,213
STA. 206+68 TO STA. 218+81 (YELLOW EDGELINE)	1,213
STA. 300+38 TO STA. 307+43 (WHITE EDGELINE)	705
STA. 300+38 TO STA. 307+43 (YELLOW EDGELINE)	705
STA. 406+96 TO STA. 418+62 (WHITE EDGELINE)	1,166
STA. 406+96 TO STA. 418+62 (YELLOW EDGELINE)	1,166
NBL REST AREA RAMPS:	
STA. 107+12 TO STA. 108+75 (WHITE EDGELINE)	163
STA. 107+12 TO STA. 108+75 (YELLOW EDGELINE)	163
STA. 134+10 TO STA. 135+34 (WHITE EDGELINE)	124
STA. 134+10 TO STA. 135+34 (YELLOW EDGELINE)	124
SBL REST AREA RAMPS:	
STA. 107+08 TO STA. 108+60 (WHITE EDGELINE)	152
STA. 107+08 TO STA. 108+60 (YELLOW EDGELINE)	152
STA. 134+30 TO STA. 135+71 (WHITE EDGELINE)	141
STA. 134+30 TO STA. 135+71 (YELLOW EDGELINE)	141
IL 143 RAMPS:	
STA. 100+34 TO STA. 110+05 (WHITE EDGELINE)	971
STA. 100+34 TO STA. 110+05 (YELLOW EDGELINE)	971
STA. 206+99 TO STA. 219+46 (WHITE EDGELINE)	1,247
STA. 206+99 TO STA. 219+46 (YELLOW EDGELINE)	1,247
STA. 300+34 TO STA. 310+21 (WHITE EDGELINE)	987
STA. 300+34 TO STA. 310+21 (YELLOW EDGELINE)	987
STA. 406+75 TO STA. 418+32 (WHITE EDGELINE)	1,157
STA. 406+75 TO STA. 418+32 (YELLOW EDGELINE)	1,157
TOTAL =	17,604