

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			ACNHF CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000-2A 80%FED/20%ST	SIGNALS E. MAIN ST. Y031-1F 100% STATE	SIGNALS E. CLAY ST. Y031-1F 80%FED/10%ST 10% CITY	TE LIGHTING Y030-1E 80%FED 20% CITY	ACNHF UTILITIES Y060 80%FED/20%ST
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	31	31				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	16883	16883				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	396	396				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	3359	3359				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	208	208				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2425	2425				
72000100	SIGN PANEL - TYPE 1	SQ FT	243	186	27.5	29.5		
72000105	SIGN PANEL - TYPE 1 (SPECIAL)	SQ FT	12	12				
72000200	SIGN PANEL - TYPE 2	SQ FT	10		10			
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	32	32				
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	8	8				
72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	153	153				
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	208	208				
72800105	TELESCOPING STEEL SIGN SUPPORT (SPECIAL)	FOOT	208	208				
73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	9	9				
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	361	361				
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6611	6611				
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	396	396				
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1991	1991				
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	208	208				
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	108	108				
78300100	PAVEMENT MARKING REMOVAL	SQ FT	4101	4101				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	53	53				
80300100	LOCATING UNDERGROUND CABLE	FOOT	300		100	100	100	
80400105	ELECTRIC SERVICE INSTALLATION, SPECIAL	EACH	1				1	
80500100	SERVICE INSTALLATION, TYPE A	EACH	2		1	1		
81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	2232		216	207	1809	
81012400	CONDUIT IN TRENCH, 1 1/4" DIA., PVC	FOOT	687				687	
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	774		369	405		
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	196		45	151		

\* SPECIALTY ITEMS

FILE NAME =	USER NAME = keplarcl	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	DRAWN -	REVISED -	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\pwidot\keplarcl\d0166772\d87d54-shr-plan.dgn	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -			600	60-(30,31,128)-N-1	MADISON	152	7		
PLOT DATE = 6/25/2010	DATE -	REVISED -				SCALE: _____ SHEET NO. 4 OF 7 SHEETS STA. _____ TO STA. _____		CONTRACT NO. 76D54				
								FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				