

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			ACNHF CONSTRUCTION TYPE CODE ACNHF						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000-2A 80%FED/20%ST	SIGNALS E. MAIN ST. Y031-1F 100% STATE	SIGNALS E. CLAY ST. Y031-1F 80%FED/10%ST 10% CITY	TE LIGHTING Y030-1E 80%FED 20% CITY	UTILITIES Y060 80%FED/20%ST	
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	678		307	371			
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	27		11	16			
81021300	CONDUIT PUSHED, 1" DIA., PVC	FOOT	754				754		
81021310	CONDUIT PUSHED, 1 1/4" DIA., PVC	FOOT	372				372		
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	13		7	6			
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	2		1	1			
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	4588				4588		
81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	7126				7126		
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	7810				7810		
81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	1338				1338		
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	4170		843	999	2328		
83600120	LIGHT POLE FOUNDATION (SPECIAL)	FOOT	294				294		
84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	2				2		
84200804	REMOVAL OF POLE FOUNDATION	EACH	2				2		
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2				2		
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	2		1	1			
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	2		1	1			
85900100	TRANSCEIVER	EACH	1		1				
86000100	MASTER CONTROLLER	EACH	1			1			
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	2629		1178	1451			
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2768		1178	1590			
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	4590		2155	2435			
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	3640		1640	2000			
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	5292		2351	2941			
87301715	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 18 6 PAIR	FOOT	500		250	250			
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	95		45	50			

\* SPECIALTY ITEMS

FILE NAME =	USER NAME = keplarc1	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cd:\pw_work\pwsdot\keplarc1\d8166772\d878d54-sht-plan.dgn	d54-sht-plan.dgn	DRAWN -	REVISED -			600	60-(30,31,128)-N-1	MADISON	152	8	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			SCALE: _____ SHEET NO. 5 OF 7 SHEETS STA. _____ TO STA. _____					
PLOT DATE = 6/25/2010		DATE -	REVISED -			CONTRACT NO. 76D54 FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT					