

SIGN REMOVAL SCHEDULE				
LOCATION	SIDE	REMOVE SIGN PANEL ASSEMBLY TYPE A (EA)	REMOVE SIGN PANEL ASSEMBLY TYPE B (EA)	REMOVE SIGN PANEL TYPE 1 (SQ FT)
IL RTE 159				
157+51	LT			2
157+51	LT			5
162+72	LT			4
162+72	LT			2.2
162+72	LT			4
162+72	LT			5
162+72	LT			2.2
163+33	RT			2
163+33	RT			5
163+33	RT			5
163+48	LT		1	
164+30	RT	1		
164+50	LT	1		
165+45	LT	1		
165+77	RT	1		
166+60	RT			6.3
166+64	LT		1	
167+68	LT	1		
168+34	RT	1		
E MAIN ST				
36+86	LT	1		
36+86	RT	1		
38+80	RT		1	
38+80	RT	1		
39+43	RT	1		
39+44	LT		1	
39+47	RT			3
40+27	RT			5
40+68	LT	1		
40+71	RT	1		
41+32	LT	1		
41+66	RT		1	
41+91	LT		1	
42+17	LT			6.2
N MORRISON AVE				
10+40	RT			3
10+40	RT			6.3
10+42	LT			4
10+75	RT	1		
10+91	LT	1		
10+91	LT		1	
11+27	RT	1		
11+62	LT	1		
12+02	RT			3
12+02	RT			4
12+02	RT			3
12+02	RT			4
12+25	LT	1		
12+25	LT			5
12+51	RT	1		
13+10	LT			2
13+10	LT			5
13+10	LT			1
E CLAY ST				
47+88	LT	1		
48+33	LT			2
48+33	LT			5
48+33	LT			2.2
48+33	LT			5
48+33	LT			2.2
48+87	RT			4
49+05	LT	1		
49+81	RT	1		
49+96	LT			5
50+05	RT		1	
50+38	RT	1		
51+05	LT			4
51+10	RT	1		
51+19	LT			4
51+57	RT	1		
51+58	LT			3
E JOHNSON ST				
11+60	RT	1		
12+33	LT	1		
12+35	LT	1		
VANDALIA ST				
10+52	LT			2
10+52	LT			5
10+52	LT			2.2
10+88	LT	1		
11+13	RT	1		
11+15	LT	1		
11+67	RT	1		
13+58	RT			4
13+58	RT			6.3
TOTAL		32	8	153

CURB & GUTTER REMOVAL SCHEDULE				
LOCATION	SIDE	CC&G REMOVAL (FT)	CURB REMOVAL (FT)	
IL RTE 159				
156+11.92 TO 157+62.90	LT	156		
156+13.88 TO 157+72.59	RT	164		
162+64.76 TO 162+97.83	LT	37		
163+06.68 TO 163+52.04	RT	54		
163+36.47 TO 163+52.02	LT	19		
163+75.78 TO 166+59.04	RT		300	
163+87.16 TO 164+11.43	LT	24		
164+45.66 TO 166+77.35	LT	231		
167+19.94 TO 168+45.60	RT	129		
167+21.31 TO 167+65.00	LT	45		
E MAIN ST				
38+74.87 TO 39+55.38	LT	83		
38+75.12 TO 39+56.49	RT	93		
40+03.05 TO 41+59.45	LT	178		
40+04.87 TO 41+59.98	RT	156		
N MORRISON AVE				
10+29.08 TO 11+18.03	RT	90		
10+30.64 TO 11+83.24	LT	156		
VANDALIA ST				
11+97.33 TO 13+68.73	LT	172		
12+63.76 TO 13+70.17	RT	108		
E CLAY ST				
48+21.69 TO 50+15.06	LT	210		
48+25.90 TO 49+81.77	RT	173		
50+31.05 TO 51+64.00	RT	141		
50+82.83 TO 51+64.06	LT	86		
E JOHNSON ST				
11+00.00 TO 11+70.57	LT	72		
11+00.00 TO 11+71.45	RT	73		
12+21.85 TO 12+61.25	RT	49		
12+24.18 TO 12+77.00	LT	54		
12+81.80 TO 12+85.93	RT	12		
TOTAL		2765	300	

STORM SEWER REMOVAL SCHEDULE			
LOCATION	10" (FT)	12" (FT)	
IL RTE 159	10	82	
E MAIN ST		228	
E CLAY ST (WEST)		53	
E CLAY ST (EAST)		87	
E JOHNSON ST		325	
TOTAL	10	775	

DRIVEWAY PAVEMENT REMOVAL SCHEDULE			
LOCATION	SIDE	TYPE	DRIVEWAY PAVEMENT REMOVAL (SQ YD)
IL RTE 159			
162+67.59 TO 163+37.97	LT	BIT	21
163+17.33	LT	CONC	31
163+33.76 TO 164+57.66	LT	BIT	212
163+63.96	RT	CONC	28
163+67.44	LT	CONC	51
164+26.48	LT	CONC	52
ALLEY 156+02			
11+00.92 TO 11+68.08	LT	BIT	103
N MORRISON AVE			
11+83.02	RT	CONC	39
13+32.68	RT	CONC	51
E CLAY ST			
49+27.99 TO 50+10.92	LT	BIT	30
49+71.01	LT	CONC	34
TOTAL			653

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL			
LOCATION	RAISED REFLECTIVE PAVEMENT MARKERS		
	ONE WAY CRYSTAL MARKER (EA)	TWO WAY AMBER MARKER (EA)	
E MAIN ST			
40+69 TO 42+72	5		
E CLAY ST			
47+70 TO 79+27		6	
50+41 TO 51+64		4	
IL RTE 159			
162+81 TO 167+00		22	
VANDALIA ST			
10+27 TO 13+57	8		
N MORRISON AVE			
10+37 TO 13+64	8		
TOTAL		53	

MANHOLE AND INLET REMOVAL SCHEDULE			
LOCATION	OFFSET	MANHOLE (EACH)	INLET (EACH)
IL RTE 159			
157+55	33' LT		1
157+64	30' LT	1	
166+78	22' LT	1	
166+84	267' RT	1	
166+84	39' LT		1
E CLAY ST			
48+33	25' RT		1
50+77	18' RT		1
TOTAL		3	4

MEDIAN REMOVAL SCHEDULE		
LOCATION	SIDE	MEDIAN REMOVAL (SQ FT)
IL RTE 159		
162+22.44	RT	110
E MAIN ST		
41+91.13	LT	176
TOTAL		286

PAVEMENT REMOVAL SCHEDULE	
LOCATION	PAVEMENT REMOVAL (SQ YD)
IL RTE 159	
155+69.56 TO 157+97.29	929
162+80.43 TO 167+65.00	2244
ALLEY 156+02.00	
10+85.00 TO 11+74.86	235
12+22.57 TO 12+75.00	148
E MAIN ST	
38+74.99 TO 39+59.42	445
39+99.46 TO 41+99.67	1083
N MORRISON AVE	
10+00.00 TO 13+77.92	1678
VANDALIA ST	
10+23.90 TO 13+76.63	1585
E CLAY ST	
47+70.00 TO 51+64.02	1713
E JOHNSON ST	
11+00.00 TO 11+76.66	276
12+16.78 TO 12+77.00	208
TOTAL	10545

EARTHWORK SCHEDULE				
LOCATION	EARTH EXCAVATION (CY)	EXCAVATION ADJUSTED FOR SHRINKAGE (CY)	EMBANKMENT (CY)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CY)
IL RTE 159	6085	4563	99	4465
ALLEY 156+02	63	47		47
E MAIN ST	470	352	4	348
E CLAY ST	716	537	2	535
E JOHNSON ST	303	227	2	225
PARKING LOT 1	475	356	1	355
PARKING LOT 2	328	246	121	125
PARKING LOT 3	199	149	15	134
TOTAL	8638	6479	244	6235

SIDEWALK REMOVAL SCHEDULE		
LOCATION	SIDE	SIDEWALK REMOVAL (SQ FT)
IL RTE 159		
156+11.66 TO 157+59.65	LT	1224.6
156+13.87 TO 157+68.91	RT	1347.0
162+66.17 TO 163+66.60	LT	633.1
163+11.72 TO 165+53.54	RT	2416.4
163+80.31 TO 164+16.20	LT	212.9
164+40.24 TO 166+78.49	LT	1971.9
167+17.55 TO 168+47.00	RT	728.6
167+21.14 TO 167+65.00	LT	408.6
E MAIN ST		
38+90.00 TO 39+51.52	LT	851.9
38+90.06 TO 39+52.46	RT	1211.6
40+08.07 TO 41+56.79	LT	2028.6
40+09.03 TO 41+60.00	RT	1692.3
N MORRISON AVE		
10+32.99 TO 11+69.43	RT	1914.3
10+34.05 TO 10+68.98	LT	393.5
11+94.82 TO 13+15.90	RT	1705.1
VANDALIA ST		
11+49.34 TO 13+66.25	LT	382.5
13+38.28 TO 13+67.52	RT	321.0
E CLAY ST		
48+22.46 TO 50+12.99	LT	1948.0
48+32.88 TO 49+78.65	RT	2209.7
50+34.20 TO 51+64.10	RT	1120.4
50+87.66 TO 51+45.92	LT	1184.6
E JOHNSON ST		
11+00.00 TO 11+63.74	RT	239.1
12+30.62 TO 12+81.95	RT	206.2
TOTAL		26352