

SIGNING SCHEDULE								
LOCATION	OFFSET	TYPE	SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 1 SPECIAL (SQ FT)	TELESCOPING STEEL SIGN SUPPORT (SPECIAL) (FT)	DECORATIVE SIGN POST (EA)	BASE FOR TELESCOPING STEEL SIGN SUPPORT (EA)	COMMENTS
IL RTE 159								
157+35	86' RT	R7-8A	1.5		14			
159+37	40' RT	M3-1	3.2		15		1	
		M1-1100	5.0					
		XM-31		6.0				
159+65	32' LT	R2-1	7.5		10		1	
	36' RT	R2-1	7.5		10		1	
160+76	32' LT	M3-3	3.2		15		1	
		M1-1100	5.0					
		XM-31		6.0				
160+06	36' RT	R3-7 R	6.3		10		1	
ALLEY 156+02								
11+58	17' RT	R1-1	9.0			1		
12+43	17' LT	R1-1	9.0			1		
12+47	23' LT	R1-1	9.0			1		
	23' LT	SPECIAL	5.0					MUNICIPAL PARKING LOT
E MAIN ST								
39+30	20' RT	W11A-2	9.0		10		1	
		R5-1	9.0					
39+30	29' LT	W11A-2	9.0		10		1	
		R5-1	9.0					
41+53	35' LT	R1-1	9.0			1		
41+99	26' RT	W11A-2	9.0		10		1	
42+13	27' LT	W11A-2	9.0		10			
N MORRISON AVE								
11+58	13' LT	R7-8A	1.5		14			
11+58	5' RT	R7-8A	1.5		14			
13+05	22' RT	R6-2r	3.0		14			
13+53	25' RT	R1-1	9.0			1		
		SPECIAL	5.0					MUNICIPAL PARKING LOT
VANDALIA ST								
10+55	22' RT	SPECIAL	5.0		10		1	MUNICIPAL PARKING LOT
11+71	62' LT	R7-8A	1.5		14			
11+81	8' LT	R6-2r	3.0		14			
11+89	54' LT	R7-8A	1.5		14			
E JOHNSON ST								
11+47	23' RT	R1-1	9.0			1		E JOHNSON ST
		W17-1100	1.5					VANDALIA ST
		W17-1100	1.5					
12+54	20' LT	R1-1	9.0			1		
TOTAL			186	12	208	7	9	

TREE FRAME AND GRATE SCHEDULE				
LOCATION	SIDE	TREE FRAME AND GRATE (EA)	REMOVE AND RELOCATE TREE FRAME AND GRATE (EA)	NOTES
IL RTE 159				
156+60	RT	1		
157+10	RT	1		
E MAIN ST				
39+05	RT		1	RELOCATE FROM MAIN ST STA 39+90 RT
39+05	LT		1	RELOCATE FROM MAIN ST STA 39+90 LT
TOTAL		2	2	

PATCHING SCHEDULE						
LOCATION	SIDE	APPROXIMATE SIZE FT X FT	PAVEMENT PATCHING, TYPE II, 17" (SQ YD)		PAVEMENT PATCHING, TYPE IV, 17" (SQ YD)	
			STAGE II	STAGE III	STAGE II	STAGE III
IL 159						
168+36.62	LT/RT	6 X 36			29	
E MAIN ST						
38+70.58	RT	9.0 X 13.0	11			
42+00.00 TO 42+74.30	RT	6.0 X 72.0			52	
E CLAY ST						
47+64.88	RT	7.0 X 10.0		8		
TOTAL			19		81	

TEMPORARY PAVEMENT SCHEDULE				
LOCATION	SIDE	HMA SURFACE COURSE, MIX "D", N90, 1 1/2" (TON)	HMA BINDER COURSE, IL-19.0, N90, 9 1/4" (TON)	
IL RTE 159				
162+14.56 TO 162+29.57	RT	1.0	6.3	
164+25.19 TO 166+81.98	RT	16.3	100.4	
167+19.03 TO 168+24.16	RT	4.3	26.6	
E MAIN ST.				
41+81.88 TO 42+00.41	LT	1.6	10.1	
TOTAL		23	143	

DETECTABLE WARNINGS		
LOCATION	SIDE	DETECTABLE WARNINGS (SQ FT)
IL RTE 159		
156+17	LT	8
156+25	RT	10
157+69	LT	6
157+71	RT	6
158+73	RT	8
162+92	LT	8
163+17	RT	44
164+04	LT	10
164+48	LT	10
E MAIN ST		
39+38	LT	6
39+38	RT	6
40+63	RT	6
41+31	LT	8
E CLAY ST		
48+25	LT	10
48+34	RT	10
48+37	LT	10
49+08	RT	8
49+45	LT	8
50+61	RT	8
E JOHNSON ST		
11+60	LT	10
11+60	RT	10
12+41	LT	10
12+41	RT	10
PARKING LOT 1	N/A	10
PARKING LOT 2	N/A	10
PARKING LOT 3	N/A	10
	N/A	10
TOTAL		270

PAVEMENT SCHEDULE														
LOCATION	POLYMERIZED HMA SURFACE COURSE, MIX E, N90 (TON)			HMA BINDER COURSE, IL-19.0, N90 (TON)				AGGREGATE BASE COURSE, TYPE A (SQ YD)		PCC BASE COURSE, 11.5" (SQ YD)	HMA SURFACE REMOVAL, VARIABLE DEPTH (SQ YD)	BITUMINOUS MATERIALS (PRIME COAT) (TON)	AGGREGATE (PRIME COAT) (TON)	AGGREGATE FOR TEMPORARY ACCESS (TON)
	1.5"	2.0"	2.5"	1.5"	2.25"	4"	6.25"	11.5"	8"					
IL 159														
155+69.56 TO 167+65.00			1019.9					4691.5	7680.8			2.28	14.6	
167+65.00 TO 168+46.50			53.5					8.4	18.4	5.3	363.8	0.12	0.8	
ALLEY 156+02														221.4
10+85.00 TO 11+72.70		25.2							233.3			0.07	0.4	
12+27.77 TO 12+75.00		15.4							144.9			0.04	0.3	
E MAIN ST														
36+80.00 TO 38+75.00	83.3										992.0			
38+75.00 TO 39+73.94	39.7							165.6	539.2			0.15	0.9	
40+37.39 TO 42+00.07	87.6							365.1	1134.8			0.33	2.1	
42+00.07 TO 42+72.00	32.8										390.7			
E CLAY ST														39.0
47+70.00 TO 49+68.36	124.9							520.3	1591.2			0.47	3.0	
50+31.64 TO 51+64.00	63.1							263.1	844.0			0.24	1.5	
E JOHNSON ST														177.4
11+00.00 TO 11+76.48		38.1			42.9				399.8			0.11	0.7	
12+23.40 TO 12+77.00		28.6			32.2				302.5			0.08	0.5	
PARKING LOT 1	51.4			51.4					648.3			0.19	1.2	418.2
PARKING LOT 2	126.7			126.7					1579.3			0.47	3.0	
PARKING LOT 3	111.5			111.5					1388.0			0.42	2.7	
TOTAL		1902			6460			8805	7699	5	1746	5.0	31.7	856