

STRIPING SCHEDULE												
LOCATION	TYPE	THERMOPLASTIC PAVEMENT MARKING						RAISED REFLECTIVE PAVEMENT MARKERS				
		LETTERS & SYM (SQ FT)	4" STRIPE		6" STRIPE	12" STRIPE		24" STRIPE	ONE WAY CRYSTAL (EA)	ONE WAY AMBER (EA)	TWO WAY AMBER (EA)	
			WHITE (FT)	YELLOW (FT)	WHITE (FT)	WHITE (FT)	YELLOW (FT)	WHITE (FT)				
IL RTE 159 151+77.16 TO 157+71.91	LETTERS AND SYMBOLS YELLOW DIAGONAL CROSSWALK STOP BAR SKIP DASH DOUBLE SOLID YELLOW SOLID WHITE	31.2				159	60		29	14	8	4
158+56.24 TO 162+06.01	LETTERS AND SYMBOLS WHITE DIAGONAL STOP BAR SKIP DASH DOUBLE SOLID YELLOW SOLID WHITE	93.6					97		67	16		8
162+89.84 TO 168+46.50	WHITE DIAGONAL YELLOW DIAGONAL CROSSWALK STOP BAR SKIP DASH DOUBLE SOLID YELLOW SOLID WHITE					271	26		33	6	6	17
ALLEY 157+00 10+85.00 TO 11+69.38	CROSSWALK STOP BAR					64			12			
11+69.38 TO 12+78.71	CROSSWALK STOP BAR					65			12			
MAIN ST 36+80.00 TO 39+40.73	LETTERS AND SYMBOLS CROSSWALK STOP BAR SKIP DASH SOLID WHITE	114.4				70			33	7		
40+60.32 TO 42+72.00	LETTERS AND SYMBOLS WHITE DIAGONAL CROSSWALK STOP BAR DOUBLE SOLID YELLOW SOLID WHITE	15.6				45	145		22			5
CLAY ST 47+50.00 TO 49+44.67	LETTERS AND SYMBOLS WHITE DIAGONAL CROSSWALK STOP BAR SOLID WHITE DOUBLE SOLID YELLOW	83.2				162	420	46		3	6	
50+57.57 TO 51+64.00	YELLOW DIAGONAL CROSSWALK STOP BAR DOUBLE SOLID YELLOW					115	26		24			5
JOHNSON ST 11+00.00 TO 11+63.12	CROSSWALK STOP BAR DOUBLE SOLID YELLOW					105		19				2
12+37.88 TO 12+77.00	CROSSWALK STOP BAR DOUBLE SOLID YELLOW					94		16				1
PARKING LOT 1	SOLID WHITE LETTERS AND SYMBOLS	4.6	293									
PARKING LOT 2	SOLID WHITE CROSSWALK LETTERS AND SYMBOLS	9.2	403			87						
PARKING LOT 3	SOLID WHITE CROSSWALK LETTERS AND SYMBOLS	9.2	530			110						
SUBTOTAL		361	4766	1845	396	1782	209	208	46	25	37	
TOTAL		361	6611	396		1991		208			108	

TEMPORARY STRIPING SCHEDULE						
LOCATION	TEMPORARY PAVEMENT MARKING (FT)					
	4" LINE		6" LINE	12" LINE		24" LINE
	SOLID WHITE	DOUBLE SOLID YELLOW	SOLID WHITE	SOLID WHITE	SOLID YELLOW	SOLID WHITE
STAGE 1	382	623		246	37	
STAGE 2 - PHASE 1	1685	188		211	27	31
STAGE 2 - PHASE 2	506	325		219	95	
STAGE 3 - PHASE 1	1907	1626		200	136	
STAGE 3 - PHASE 2	744			35		
STAGE 4 - PHASE 1	1975	1246		48	114	
STAGE 4 - PHASE 2	291					
STAGE 5	3540	1845	396	1782	209	208
SUBTOTAL	11030	5853	396	2741	618	208
TOTAL		16883	396		3359	208

CURB AND GUTTER SCHEDULE				
LOCATION	SIDE	CCC&G TYPE B-6.24 (FT)	CCC&G TYPE B-6.12 (FT)	CONCRETE CURB TYPE B (FT)
IL RTE 159 156+16.22 TO 157+70.27	LT	162.1		
156+22.81 TO 157+70.99	RT	149.5		
158+24.18 TO 161+44.56	LT	338.0		
158+55.01 TO 162+27.86	RT	368.5		
162+59.73 TO 166+72.15	LT	414.3		
163+14.90 TO 166+74.32	RT	375.1		
167+27.09 TO 168+46.50	RT	123.7		
167+28.10 TO 167+65.00	LT	40.6		
ALLEY 156+02 11+51.59 TO 11+67.35	LT	17.0		
12+32.82 TO 12+48.22	LT	18.2		
E MAIN ST 38+74.88 TO 39+68.54	LT	95.6		
38+69.16 TO 39+54.63	RT	92.5		
40+34.98 TO 41+59.99	RT	128.3		
40+86.91 TO 41+61.74	RT	118.7		
E CLAY ST 48+19.31 TO 49+80.02	LT	174.4		
48+29.40 TO 49+08.52	RT	89.6		
50+28.56 TO 51+64.00	RT	143.1		
50+83.80 TO 51+64.00	LT	89.0		
E JOHNSON ST 11+00.00 TO 11+60.49	RT	64.6		
11+00.00 TO 11+63.81	LT	67.7		
12+38.83 TO 12+77.00	RT	40.0		
12+36.69 TO 12+77.00	LT	44.2		
PARKING LOT 1	N/A		149.7	182.0
PARKING LOT 2	N/A	30.1	306.2	273.7
PARKING LOT 3	N/A		302.7	150.1
TOTAL		3184.8	758.6	606.0

SIDEWALK SCHEDULE		
LOCATION	SIDE	PCC SIDEWALK, 4" (SQ FT)
IL RTE 159 156+13.07 TO 157+68.40	LT	1117
156+21.39 TO 157+69.24	RT	750
158+25.76 TO 161+42.33	LT	1732
158+57.16 TO 162+26.56	RT	2164
162+61.89 TO 164+06.13	LT	788
163+17.13 TO 166+80.52	RT	2051
164+44.67 TO 166+84.59	LT	1756
167+24.04 TO 168+47.06	RT	716
167+23.25 TO 167+65.00	LT	399
E MAIN ST 38+69.20 TO 39+52.72	RT	1265
38+86.93 TO 39+66.93	LT	1205
40+36.73 TO 41+60.00	RT	1280
40+70.98 TO 41+59.16	LT	1109
E CLAY ST 48+22.26 TO 49+77.56	LT	991
48+29.88 TO 49+06.29	RT	406
50+29.85 TO 51+64.00	RT	1191
50+86.03 TO 51+64.00	LT	484
PARKING LOT 2	N/A	115
PARKING LOT 3	N/A	557
TOTAL		20076

SPECIAL SIDEWALK SCHEDULE		
LOCATION	SIDE	PCC SIDEWALK SPECIAL, 4" (SQ FT)
IL RTE 159 156+27 TO 157+50	RT	227
158+37 TO 161+34	LT	606
158+79 TO 162+05	RT	609
162+41 TO 162+82	LT	94
163+02 TO 164+01	LT	193
163+22 TO 163+75	RT	109
164+75 TO 166+52	RT	463
E MAIN ST 38+69 TO 39+31	RT	196
38+87 TO 39+31	LT	133
40+70 TO 41+60	RT	180
40+91 TO 41+35	LT	72
E CLAY ST 48+37 TO 49+01	RT	130
TOTAL		3012

ENTRANCE SCHEDULE						
LOCATION	SIDE	TYPE	WIDTH (FT)	PCC DRIVEWAY PAVEMENT, 8" (SQ YD)	CCC&G TYPE B 6.24 (FT)	AGGREGATE FOR TEMPORARY ACCESS (TON)
IL RTE 159 164+25.30	LT	CE	30	58.7	48.0	40.2
ALLEY 156+02 11+26.50	LT	CE	50	81.2		55.5
TOTAL				140	48.0	96

TEMPORARY RAMP SCHEDULE	
LOCATION	TEMPORARY RAMP (SQ YD)
IL RTE 159 155+69.56	50.9
167+65.00	37.0
ALLEY STA. 156+02 10+85.00	17.1
12+75.00	17.1
E MAIN ST 38+75.00	25.6
42+00.00	33.9
E CLAY ST 47+70.00	20.6
48+06.00	16.7
51+64.00	20.6
E JOHNSON ST 11+00.00	22.3
12+77.00	20.1
STAGE 2	24.2
STAGE 3	37.7
TOTAL	344

PAVEMENT IMPRINTING	
LOCATION	PAVEMENT IMPRINTING (SQ YD)
IL RTE 159 157+66 TO 157+72	52.6
162+98 TO 163+04	53.6
ALLEY @ 156+02 11+62 TO 11+68	17.0
12+32 TO 12+38	18.3
E MAIN ST 39+35 TO 39+41	23.4
40+60 TO 40+66	47.3
E CLAY ST 49+29 TO 49+35	58.8
50+67 TO 50+73	44.8
E JOHNSON ST 11+57 TO 11+63	34.8
12+38 TO 12+44	31.3
TOTAL	382

PARKING BLOCKS		
LOCATION	SIDE	PARKING BLOCKS (EACH)
PARKING LOT 2	N/A	15
TOTAL		15

STRIP REFLECTIVE CRACK CONTROL TREATMENT SCHEDULE		
LOCATION	SIDE	STRIP REFLECTIVE CRACK CONTROL TREATMENT (FT)
167+65.00 TO 168+24.20	RT	59.0
TOTAL		59.0

FILE NAME =	USER NAME = default	DESIGNED =	REVISED =
p:\projects\513501\ceda\dgn\0876054-shd	schedule.dgn	DRAWN =	REVISED =
		CHECKED =	REVISED =
		DATE = 6/15/2010	REVISED =

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES

SCALE: N/A	SHEET NO. 3 OF 9 SHEETS	STA. N/A TO STA. N/A	F.A.P. RTE 600	SECTION 60-(30,31,128)-N-1	COUNTY MADISON	TOTAL SHEETS 152	SHEET NO. 22	CONTRACT NO. 76054	ILLINOIS FED. AID PROJECT
------------	-------------------------	----------------------	----------------	----------------------------	----------------	------------------	--------------	--------------------	---------------------------