

**GUARDRAIL**

LOCATION			STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURE	TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 2	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	GUARDRAIL MARKERS	TERMINAL MARKER DIRECT APPLIED	GUARDRAIL REMOVAL
STATION	TO	STATION	(FOOT)	(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(FOOT)
PRE - STAGE I												
IL RTE 242												
657+03.40	-	662+26.50	LT									
656+00.30	-	659+00.30	RT					1				
PIOPOLIS RD. (CH 20)												
10+18.00	-	11+08.90	RT			50.0						63
SUB TOTAL - STAGE I			0.0	0.0	50.0	0	0	1	0	2	0	63
STAGE I												
IL RTE 242												
657+03.40	-	662+26.50	LT	262.5	37.5			4		8	4	154
656+00.30	-	659+00.30	RT									
PIOPOLIS RD. (CH 20)												
10+18.00	-	11+08.90	RT									
SUB TOTAL - STAGE I			262.5	37.5	0.0	0	4	0	0	8	4	154
STAGE II												
IL RTE 242												
657+03.40	-	662+26.50	LT									
656+00.30	-	659+00.30	RT	237.5	10.6				1	3	1	102
PIOPOLIS RD. (CH 20)												
10+18.00	-	11+08.90	RT	87.5	26.9		1			2	1	50
SUB TOTAL - STAGE II			325.0	37.5	0.0	1	0	0	1	5	2	152
POST STAGE II												
IL RTE 242												
657+03.40	-	662+26.50	LT									
656+00.30	-	659+00.30	RT									
PIOPOLIS RD. (CH 20)												
10+18.00	-	11+08.90	RT									
SUB TOTAL - POST STAGE II			0.0	0.0	0.0	0	0	0	0	0	0	0
TOTAL			587.5	75.0	50.0	1	4	1	1	15	6	369

\*NOTE: STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES TO BE INSTALLED FROM  
 STA. 658+97.19 TO STA. 659+34.69, LT. AND  
 STA. 658+87.81 TO STA. 658+98.40, RT. ALONG IL. RTE. 242  
 STA. 10+14.21 TO STA. 10+27.16, RT. ALONG PIOPOLIS RD.