



**STAGE II - TRAFFIC CONTROL ITEMS**

HMA SHOULDER, 10"	265	SY YD
RELOCATE TEMPORARY CONCRETE BARRIER	330	FOOT
RELOCATE TEMPORARY IMPACT ATTENUATORS	2	EACH
TRAFFIC CONTROL SURVEILLANCE	2	CAL DAY
PAVEMENT MARKING REMOVAL	103	SQ FT

**POST - STAGE II - TRAFFIC CONTROL ITEMS**

SHORT TERM PAVEMENT MARKING	188	FOOT
*TEMPORARY PAVEMENT MARKING - LINE 4"	1992	EACH
*TEMPORARY PAVEMENT MARKING - LINE 24"	23	EACH
WORK ZONE PAVEMENT MARKING REMOVAL	773	SQ FT
PAINT PAVEMENT MARKING - LINE 4"	1992	EACH
PAINT PAVEMENT MARKING - LINE 24"	23	EACH

\* NOTE: TO BE USED ONLY IF PERMANENT PAINT CANNOT BE APPLIED DUE TO SPECIFICATION REQUIREMENTS.

**LEGEND**

- WORK AREA
- HMA SHOULDER
- TEMPORARY CONCRETE BARRIER
- TEMPORARY IMPACT ATTENUATOR
- SIGN
- LIGHT, TYPE B
- TYPE III BARRICADE WITH FLASHING LIGHT

- NOTES:**
- TRAFFIC CONTROL FOR ROAD CLOSURE ALONG PIOPOLIS ROAD TO BE PROVIDED IN ACCORDANCE WITH HIGHWAY STANDARD BLR 21 AND AS SPECIFIED HEREIN, AND SHALL BE INCLUDED IN THE COST FOR TRAFFIC CONTROL PROTECTION, 701321 - EACH.
  - SIGN LOCATIONS, INCLUDING PORTABLE CHANGEABLE MESSAGE SIGN, SHALL BE DETERMINED BY THE ENGINEER.
  - SEE HIGHWAY STANDARD 701321 B.L.R. 21 FOR DETAILS NOT SHOWN.