

SIDEWALK REMOVAL 44000600

STATION TO STATION	L/R	SQ. FT.
1+17 - 1+56	L	147
1+37 - 1+45	R	22
1+73 - 2+40	L	264
1+79 - 2+26	R	161
2+60 - 2+69	R	23
2+64 - 3+97	L	617
3+22 - 4+66	R	684
4+16 - 5+79	L	973
4+92 - 5+13	R	95
6+09 - 11+86	L	2245
6+13 - 7+24	R	490
7+37 - 8+00	R	251
8+08 - 8+68	R	277
9+06 - 10+33	R	566
10+48 - 11+83	R	928
12+16 - 16+46	L	1645
12+18 - 13+57	R	1044
14+96 - 15+00	R	14
15+26 - 16+05	R	211
16+25 - 16+44	R	53
TOTAL		10710

COMB. CURB & GUTTER REMOVAL 44000500

STATION TO STATION	L/R	FT
2+72 - 3+97	L	122
3+22 - 5+13	R	191
4+16 - 16+47	L	1230
6+13 - 8+68	R	275
9+06 - 11+88	R	311
12+18 - 15+00	R	309
15+23 - 16+44	L	138
TOTAL		2576

PCC DRIVEWAY PAVEMENT, 7" 42300300

STATION TO STATION	L/R	SQ. YD.
1+37 - 1+87	R	37
2+18 - 2+69	R	37
3+57 - 3+87	R	25
4+59 - 5+00	R	40
5+71 - 6+17	L	36
6+34 - 6+66	R	26
7+12 - 7+44	R	26
7+87 - 8+19	R	24
10+24 - 10+56	R	26
11+79 - 12+19	L	29
16+00 - 16+32	R	27
TOTAL		333

DRIVEWAY PAVEMENT REMOVAL 44000200

STATION	L/R	SQ. YD.
3+20	L	6
3+67	R	11
4+71	R	13
4+84	R	9
5+94	L	40
6+51	R	8
7+31.5	R	17
8+04	R	11
10+41	R	16
11+99	L	25
16+18	R	20
TOTAL		176

PAVEMENT REMOVAL 44000100

STATION TO STATION	L/R	WIDTH (FT)	SQ. YD.
2+72 - 3+97	L	4	56
4+16 - 16+47	L	4	547
3+22 - 5+13	R	4	85
6+13 - 8+60	R	4	110
SW CORNER HOOKER AVE	R	4x20	9
SE CORNER HOOKER AVE	R	4x20	9
9+20 - 11+83	R	4	117
SW CORNER JOHANNA AVE	R	4x20	9
SE CORNER JOHANNA AVE	R	4x20	9
12+30 - 14+98	R	4	119
SW CORNER MARY AVE	R	4x15	7
SE CORNER MARY AVE	R	4x15	7
15+32 - 16+44	R	4	50
TOTAL			1134

DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED 56500600

STATION	L/R	EA.
3+41	R	1
4+05	R	1
4+56	R	1
6+31	R	1
6+74	R	1
7+64	R	1
10+21	R	1
10+68	R	1
12+95	R	1
TOTAL		9

CATCH BASIN, TYPE A, 4' DIAMETER WITH TYPE 1 FRAME, OPEN LID 60200105

STATION	L/R	EA.
15+00	R	1

GAS VALVE TO BE ADJUSTED X0322468

STATION	L/R	EA.
3+26	L	1
3+38	R	1
3+93	R	1
4+38	R	1
6+79	R	1
7+85	R	1
10+17	R	1
TOTAL		7

SUB-BASE GRANULAR MATERIAL 31100100

STATION TO STATION	L/R	SQ. YD.	TON
2+72 - 3+97	L	56	32
4+16 - 16+47	L	547	311
3+22 - 5+13	R	85	48
6+13 - 8+60	R	110	62
SW CORNER HOOKER AVE	R	7	4
SE CORNER HOOKER AVE	R	7	4
9+21 - 11+79	R	115	65
SW CORNER JOHANNA AVE	R	7	4
SE CORNER JOHANNA AVE	R	7	4
12+32 - 14+87	R	113	64
SW CORNER MARY AVE	R	7	4
SE CORNER MARY AVE	R	7	4
15+32 - 16+44	R	50	28
TOTAL			634

AGGREGATE BASE COURSE, TYPE B 35101400

STATION TO STATION	L/R	SQ. YD.	TON
1+17 - 1+56	L	28	9
1+17 - 1+45	R	15	5
1+37 - 1+87	R	50	17
1+73 - 2+40	L	33	11
1+79 - 2+26	R	32	11
2+18 - 2+69	R	50	17
2+60 - 2+82	R	15	5
2+64 - 3+97	L	109	37
3+57 - 3+87	R	27	9
4+16 - 5+80	L	141	48
4+59 - 5+00	R	27	9
5+71 - 6+17	L	42	14
6+08 - 16+47	L	919	314
3+22 - 3+57	R	33	11
3+22 - 3+29	R	3	1
3+87 - 4+59	R	70	24
3+95 - 4+04	R	5	2
5+00 - 5+32	R	28	10
5+10 - 5+13	R	1	0.5
5+89 - 6+34	R	40	14
6+26 - 6+30	R	2	0.5
6+66 - 7+12	R	48	16
6+34 - 6+66	R	27	9
7+12 - 7+44	R	27	9
7+44 - 7+87	R	44	15
7+53 - 7+56	R	1	0.5
7+87 - 8+19	R	28	10
8+19 - 8+68	R	46	16
8+17 - 8+21	R	2	0.5
9+06 - 10+24	R	112	38
9+42 - 9+47	R	2	1.0
10+04 - 10+08	R	2	0.5
10+24 - 10+56	R	27	9
10+56 - 11+88	R	120	41
11+49 - 11+53	R	2	0.5
12+18 - 15+00	R	251	86
15+23 - 16+00	R	71	24
15+38 - 15+41	R	2	0.5
15+60 - 15+64	R	2	0.5
16+00 - 16+32	R	27	9
16+26 - 16+29	R	1	0.5
16+32 - 16+44	R	16	6
TOTAL			861.5

INC HMA SURFACING 408000500

STATION TO STATION	L/R	SQ. YD.	TON
2+72 - 3+97	L	56	18
4+16 - 16+47	L	547	172
3+22 - 5+13	R	85	27
6+13 - 8+60	R	110	34
SW CORNER HOOKER AVE	R	7	2
SE CORNER HOOKER AVE	R	7	2
9+21 - 11+79	R	115	36
SW CORNER JOHANNA AVE	R	7	2
SE CORNER JOHANNA AVE	R	7	2
12+32 - 14+87	R	113	35
SW CORNER MARY AVE	R	7	2
SE CORNER MARY AVE	R	7	2
15+32 - 16+44	R	50	16
TOTAL			350

DETECTABLE WARNING 42400800

STATION	L/R	SQ. FT.
1+25	L	6
1+25	R	6
2+76	R	6
5+25	R	6
4+01	R	6
5+63	L	6
5+73	L	6
5+95	R	6
6+15	L	6
7+12	R	6
7+43	R	6
8+65	R	6
9+12	R	6
10+24	R	6
10+56	R	6
11+76	L	6
11+76	R	6
11+80	L	6
11+80	R	6
12+17	L	6
12+23	R	6
13+51	R	6
13+67	R	6
14+94	R	6
15+27	R	6
TOTAL		150

TREES

STATION	L/R	TYPE
1+89	R (IN PLANTER)	PCP
2+14	R (IN PLANTER)	PCP
3+47	R (IN PLANTER)	PCP
4+54	R (IN PLANTER)	PCP
5+05	R (IN PLANTER)	PCP
6+82	L (IN PLANTER)	PCP
7+06	R (IN PLANTER)	PCP
7+66	R (IN PLANTER)	PCP
7+91	L (IN PLANTER)	PCP
8+31	R (IN PLANTER)	PCP
8+70	L (IN PLANTER)	PCP
9+31	R (IN PLANTER)	PCP
9+56	L (IN PLANTER)	PCP
9+90	R (IN PLANTER)	PCP
10+24	L (IN PLANTER)	PCP
10+63	R (IN PLANTER)	PCP
10+92	L (IN PLANTER)	PCP
11+24	R (IN PLANTER)	PCP
11+52	L (IN PLANTER)	PCP
11+70	R (IN PLANTER)	PCP
12+32	R (IN PLANTER)	PCP
12+56	L (IN PLANTER)	PCP
13+01	R (IN PLANTER)	PCP
13+41	L (IN PLANTER)	PCP
13+90	R (IN PLANTER)	PCP
14+31	L (IN PLANTER)	PCP
14+81	R (IN PLANTER)	PCP
15+31	L (IN PLANTER)	PCP
15+69	R (IN PLANTER)	PCP
16+06	L (IN PLANTER)	PCP
16+38	R (IN PLANTER)	PCP
TOTAL		31



FEHR-GRAHAM & ASSOCIATES, LLC
ENGINEERING AND SCIENCE CONSULTANTS
FREEPORT, IL ROCKFORD, IL ROCHELLE, IL SPRINGFIELD, IL MONROE, WI
ILLINOIS DESIGN FIRM NO. 184-003525
© 2010 FEHR-GRAHAM & ASSOCIATES

OWNER/DEVELOPER:
CITY OF FREEPORT
230 W. STEPHENSON ST.
FREEPORT, IL 61032

PROJECT AND LOCATION:
STEPHENSON STREET
STREETSCAPE IMPROVEMENTS
SECTION 09-00138-00-LS

DRAWN BY: G.B.
APPROVED BY: P.E.
DATE: 06/10/10
SCALE: AS NOTED

REVISIONS		
REV. NO.	DESCRIPTION	DATE
1	REVISIONS PER IDOT REVIEW	7/12/10

DRAWING:
SCHEDULE OF QUANTITIES

G:\EPL\09\09-302\09-302-Fdports.dwg, Schedule

JOB NUMBER:
09-302

SHEET NUMBER:
4 of 9