0 10 20 40
SCALE IN FEET

MISSISSIPPI RIVER

11 LF 12" RCP SS @ 0.30%

STA. 23+30/OFFSET 15.90' LT
MH TY A, TY 1 FR. CL LID
RIM = 565.76
INV. W = 561.69
INV. E = 561.69

STA. 23+45/OFFSET 18.32 LT
MH TY A, TY 1 FR. CL LID
RIM = 566.00
INV. W = 561.65
INV. E = 561.65

SCHADLER RIVER EXCURSIONS, INC.

(2) GLED

TEMPORARY CONSTRUCTION EASEMENT

EXISTING SHARED-USE PATH

STORM SEWER REMOVAL, 15"

EXISTING SHARED USE PATH CONTINUES AROUND PARKING LOT AND IS NEAR STREET AGAIN ST STA. 27+10

CITY OF MOLINE
BEN BUTTERWORTH PARKWAY
PARKING LOT

(2) ACERM

PROPOSED PCC CURB AND GUTTER B-6.18

SAWCUT AND REMOVE HMA PAVEMENT

APPROXIMATE EXISTING RIGHT OF WAY

EXISTING SHARED USE PATH

MATCH LINE STA. 28+00

MATCH LINE STA. 22+00

RIVER DRIVE

RIVER DRIVE

APPROXIMATE EXISTING RIGHT OF WAY

PCC DRIVEWAY, 7"

SAWCUT AND REMOVE PAVEMENT
REPLACE WITH PCC CURB & GUTTER TY B-6.18
STA. 21+80 TO STA. 23+45

139LF 15" RCP SS @ 0.29%

CP507

CITY OF MOLINE

WESTERN ILLINOIS UNIVERSITY FOUNDATION

PROPOSED IMPROVEMENTS LEGEND

GENERAL SITE	
PLAN MARK	DESCRIPTION
	PORTLAND CEMENT CONCRETE
	DECORATIVE STREET LIGHT
	PROPOSED TREE
	SEEDING, CLASS 1

SHIVE-HATTERY
Cedar Rapids, IA · Iowa City, IA · Des Moines, IA
Moline, IL · Bloomington, IL · Chicago, IL
SHIVE-HATTERY, INC. 1701 RIVER DRIVE, SUITE 200 MOLINE,IL 61265
PHONE (309) 764-7650 FAX (309) 764-8616
http://www.shive-hattery.com
ILLINOIS FIRM NUMBER: 184-000214

FILE NAME = $FILE$	USER NAME = $USER$	DESIGNED - PHM	REVISED -
		DRAWN - MAC	REVISED -
	PLOT SCALE = $SCALE$	CHECKED - 07-06-10	REVISED -
	PLOT DATE = $DATE$	DATE - 07-06-10	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

RIVER DRIVE PLAN

SCALE: 1" = 20' | SHEET NO. 11 OF 30 SHEETS | STA. 22+00 TO STA. 28+00

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5756	06-00234-00-LS	ROCK ISLAND	30	11
		CONTRACT NO. 85517		
FED. ROAD DIST. NO. 2	ILLINOIS	FED. AID PROJECT		