

F.A.U. ROUTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
SCHUYLER - F.A.U. 6201	08-00094-00-TL	KANKAKEE	13	02
BROADWAY - F.A.U. 6178			CONTRACT NO.: 87370	

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: Y031-1F

	ITEM NUMBER	ITEM	UNIT	TOTAL QUANTITY		ITEM NUMBER	ITEM	UNIT	TOTAL QUANTITY
	* X2500900	SEEDING, CLASS 1 (SPECIAL)	ACRE	0.15		87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	1
	△ 35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	113		87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1
△	* 40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	401		87702860	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 26 FT.	EACH	1
	△ 40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	56		87702950	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT.	EACH	1
	△ 40603340	HOT MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	281		87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8
	△ 42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,013		* 87800152	CONCRETE FOUNDATION, TYPE C (SPECIAL)	FOOT	4
	△ 42400800	DETECTABLE WARNINGS	SQ FT	12		* 87800410	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER (SPECIAL)	FOOT	30
△	* 44000100	PAVEMENT REMOVAL	SQ YD	613		* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	15
△	* Z0004548	HOT MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	3,447		88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	4
	△ 44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	506		88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	5
	△ 44000800	SIDEWALK REMOVAL	SQ FT	714		88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1
	△ 44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	617		88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	1
△	* Z0004554	BARRIER MEDIAN REMOVAL	SQ FT	2,241		88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2
△	* Z0037310	PAVEMENT PATCHING (FULL DEPTH)	SQ YD	570		88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	11
	△ 550B0040	STORM SEWERS, CLASS B, TYPE 1 10"	FOOT	68		* 88500100	INDUCTIVE LOOP DETECTOR	EACH	9
	△ 55100300	STORM SEWER REMOVAL 8"	FOOT	55		88600100	DETECTOR LOOP, TYPE I	FOOT	1,002
△	* 60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	1		88700200	LIGHT DETECTOR	EACH	2
	△ 60255500	MANHOLES TO BE ADJUSTED	EACH	5		88700300	LIGHT DETECTOR AMPLIFIER	EACH	1
	△ 60500060	REMOVING INLETS	EACH	1		88800100	PEDESTRIAN PUSH-BUTTON	EACH	2
△	* 60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	588		X0325969	PORTABLE, VEHICLE MOUNTED, CHANGEABLE MESSAGE BOARD	CAL DA	85
△	* 60611599	COMBINATION CONCRETE CURB AND GUTTER, (MODIFIED)	FOOT	93		△ * X0350810	BOLLARD REMOVAL	EACH	25
	67100100	MOBILIZATION	L SUM	1		* X8050010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	1
	* 70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1		* X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	1
	72000100	SIGN PANEL - TYPE 1	SQ FT	8		* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	374
	72000200	SIGN PANEL - TYPE 2	SQ FT	45		X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	250
	72900200	METAL POST - TYPE B	FOOT	30		△ * Z0004510	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3"	SQ YD	57
△	78001100	PAINT PAVEMENT MARKING - LETTER AND SYMBOLS	SQ FT	47		* SEE SPECIAL PROVISIONS			
△	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2,744		△ SPECIALTY ITEMS			
△	78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	120					
△	78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	84					
	81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	231					
	81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	256					
	81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	13					
	81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	29					
	81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	20					
	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	165					
*	81021330	CONDUIT PUSHED, 2" DIA., PVC	FOOT	390					
*	81021350	CONDUIT PUSHED, 3" DIA., PVC	FOOT	87					
*	81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	6					
*	81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1					
	81702450	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 10	FOOT	252					
	81800200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	288					
	82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	2					
	84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	5					
*	84200804	REMOVAL OF POLE FOUNDATION	EACH	5					
*	85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1					
	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	138					
	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	152					
	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1,410					
	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	183					
	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1,628					
	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	98					

* SEE SPECIAL PROVISIONS



REVISIONS		
DATE	BY	DESCRIPTION
01-05-2008	JWG	PER IDOT REVIEW
07-15-2008	JWG	PER IDOT REVIEW

ILLINOIS DEPARTMENT OF TRANSPORTATION
SAFE ROUTES TO SCHOOLS
BROADWAY & SCHUYLER INTERSECTION SIGNALS

SUMMARY OF QUANTITIES

SCALE: _____ DRAWN BY: JWG
DATE: 12/21/08 CHECKED BY: _____