

**SUMMARY OF QUANTITIES**

NO.	DESCRIPTION	HBP ITEMS		NON-PARTICIPATING (LOCAL FUNDS ONLY) ITEMS	
		X080 - 2A		Y007	
		UNIT	TOTAL QTY.	UNIT	TOTAL QTY.
35101400	AGGREGATE BASE COURSE, TYPE B	TON	24		
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	51		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX 'C', NSO	TON	79		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	153		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FDDT	44		
44000600	SIDEWALK REMOVAL	SQ FT	146		
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	36		
* 50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		
50102400	CONCRETE REMOVAL	CU YD	2.1		
* <del>50300300</del> 50300305	CONCRETE REMOVAL (SPECIAL)	EACH	4		
50300100	FLOOR DRAINS	EACH	20		
50300225	CONCRETE STRUCTURES	CU YD	2.2		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	46		
50300300	PROTECTIVE COAT	SQ YD	179		
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21' DEPTH)	SQ FT	5119		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3450		
Δ 50900405	STEEL RAILING, TYPE TP-1	FDDT	228		
51500100	NAME PLATES	EACH	1		
* 51500200	RELOCATING NAME PLATES	EACH	1		
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	468		
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FDDT	1595		
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FDDT	44		
67100100	MOBILIZATION	L SUM	1		
* 70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1		
Δ 78001130	PAINT PAVEMENT MARKING - LINE 6'	FDDT	369		
* 20001900	ASBESTOS BEARING PAD REMOVAL	EACH	52		
* X0300558	SANITARY SEWER REMOVAL AND REPLACEMENT 8"	FOOT	-	FOOT	62.50

\* SEE SPECIAL PROVISIONS  
 Δ SPECIALTY ITEMS

FILE NAME = 003-SUMQUAN.DWG	USER NAME =	DESIGNED - J.K.C.	REVISED -	<b>FAU 5958 (OTTAWA AVENUE) SECTION 07-00137-00-BR GRUNDY COUNTY</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - L.A.G.	REVISED -		5958	07-00137-00-BR	GRUNDY	11	3			
		CHECKED - J.K.C.	REVISED -		CONTRACT NO. 87463			FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				
		DATE - 04/10	REVISED -		SCALE: NONE	SHEET NO. 3 OF 11 SHEETS	STA. _____ TO STA. _____					